

BRUCE ERNST ASPHALT INC.  
14461 ROAD C  
WAUSEON, OHIO 43567

PHONE: 419/337-6871  
FAX: 419/337-3504  
E-MAIL: ERNSTASPHALT@YAHOO.COM

**BID**

*AAn TIA  
592-5508*

DATE: 05/04/09

TO: Ridgeville Township Trustees

FOR: Seal Coat of various Township Roads

*FOR CHAIR*

Township Road U from Road 19 to Road X			
423	- Seal coat bituminous material @ .4 gal./s.y. - 1242 gal. @ 2.05/gal.	=	2,546.10
423	- Washed No. 8 Cover Ag. @ 24 lbs./s.y. - 35 c.y. @ 23.09/c.y.	=	808.15
614	- Maintaining traffic - lump sum	=	<u>100.00</u>
Road U Total			= \$3,454.25

Township Road V from Road 19 to Road 20			
423	- Seal coat bituminous material @ .4 gal./s.y. - 3474 gal. @ 2.05/gal.	=	7,121.70
423	- Washed No. 8 Cover Ag. @ 24 lbs./s.y. - 90 c.y. @ 23.09/c.y.	=	2,078.10
614	- Maintaining traffic - lump sum	=	<u>100.00</u>
Road V Total			= \$9,299.80

Township Road 21A from S.R. 34 to Road V			
423	- Seal coat bituminous material @ .4 gal./s.y. - 7798 gal. @ 2.05/gal.	=	15,985.90
423	- Washed No. 8 Cover Ag. @ 24 lbs./s.y. - 195 c.y. @ 23.09/c.y.	=	4,502.55
614	- Maintaining traffic - lump sum	=	<u>100.00</u>
Road 21A Total			= \$20,588.45

Total All Seal Coat = \$33,342.50

BRUCE ERNST ASPHALT INC.  
14461 ROAD C  
WAUSEON, OHIO 43567

PHONE: 419/337-6871  
FAX: 419/337-3504  
E-MAIL: ERNSTASPHALT@YAHOO.COM

**BID**

DATE: 05/04/09

TO: Ridgeville Township Trustees

FOR: Crack seal on various Township Roads

Township Road V from C.R. 24 to C.R. 25  
423 - Crack seal on approx. 6110 s.y. @ \$0.448/s.y. = 2,737.28

Township Road 22 from C.R. U1 to C.R. W  
423 - Crack seal on approx. 16,510 s.y. @ \$0.448/s.y. = 7,396.48

Township Road V from C.R. 21 to C.R. 22  
423 - Crack seal on approx. 7,060 s.y. @ \$0.448/s.y. = 3,162.88

Total project = \$13,296.64

BRUCE ERNST ASPHALT INC.  
14461 ROAD C  
WAUSEON, OHIO 43567

PHONE: 419/337-6871  
FAX: 419/337-3504  
E-MAIL: ERNSTASPHALT@YAHOO.COM

**ESTIMATE**

DATE: 05/04/09

TO: RidgevilleTownship Trustees

FOR: Dustdown

Road 22A from S.R. 6 South:

408 - Bituminous Prime for dustdown - 200 gal. @ \$2.10 = \$420.00

Estimates are generally considered to be within 10% of the final project, exclusive of approved changes. Final charges are based upon actual quantities used as measured by freight bills, weight slips, etc.