

**2010 Ridgeville Township Road Improvement Bid Tab**

Ref. No.	Item No.	Quantity	Units	Item	Jennite Company		Gerken Asphalt	
					Unit Price	Total	Unit Price	Total
Road X from US 6 to Road T Length: 2,750 L.F. or 0.52 miles Width: 20' widen to 22 feet (7,140 S.Y. including driveway/mailbox approaches and radius work) Type: 448 Surface Course w/ 617 Berm @ 24" wide each side.								
1	201	3	Each	Tree & Stump Removal (24" diameter)	\$ 700.00	\$ 2,100.00	\$ 700.00	\$ 2,100.00
2	202	12	Each	Remove & Relocate Mailbox/Paperbox/Street Sign	\$ 30.00	\$ 360.00	\$ 180.00	\$ 2,160.00
3	203	85	CY	Excavation for Widening including Embankment	\$ 12.00	\$ 1,020.00	\$ 63.00	\$ 5,355.00
4	204	615	SY	Subgrade Compaction	\$ 0.95	\$ 584.25	\$ 0.50	\$ 307.50
5	253	10	CY	Pavement Repair	\$ 175.00	\$ 1,750.00	\$ 270.00	\$ 2,700.00
6	301	85	CY	Asphalt Concrete Base Placed and Compacted at depth of 5"	\$ 131.00	\$ 11,135.00	\$ 145.00	\$ 12,325.00
7	407	360	Gal	Bituminous Tack Coat Applied to Existing Pavement at Rate of 0.05 Gallons Per Square Yard	\$ 3.00	\$ 1,080.00	\$ 2.00	\$ 720.00
8	448	300	CY	Asphalt Concrete Surface Course, PG 64-22, Type 1M Applied, Spread and Compacted at the Average Depth of 1 1/2"	\$ 138.00	\$ 41,400.00	\$ 125.00	\$ 37,500.00
9	617	70	CY	Stabilized Crushed Aggregate Berm in place and compacted at the average depth of 2"	\$ 28.00	\$ 1,960.00	\$ 48.00	\$ 3,360.00
10	604	5	Each	Manholes Adjusted to Grade	\$ 210.00	\$ 1,050.00	\$ 700.00	\$ 3,500.00
11	609	100	Ft	Combination Curb & Gutter, Type 2	\$ 21.00	\$ 2,100.00	\$ 50.00	\$ 5,000.00
12	Spec.	3	Each	Formed Construction Joint (3 @ 217 L.F.)	\$ 700.00	\$ 2,100.00	\$ 360.00	\$ 1,080.00
Road X from Road T to Road U Length: 6,670 L.F. or 1.26 miles Width: 20' (15,005 S.Y. including driveway/mailbox approaches and radius work) Type: 448 Surface Course w/ 617 Berm @ 36" wide each side								
13	407	750	Gal	Bituminous Tack Coat Applied to Existing Pavement at Rate of 0.05 Gallons Per Square Yard	\$ 3.00	\$ 2,250.00	\$ 2.00	\$ 1,500.00
14	448	625	CY	Asphalt Concrete Surface Course, PG 64-22, Type 1M Applied, Spread and Compacted at the Average Depth of 1 1/2"	\$ 138.00	\$ 86,250.00	\$ 125.00	\$ 78,125.00
15	617	250	CY	Stabilized Crushed Aggregate Berm in place and compacted at the average depth of 2"	\$ 28.00	\$ 7,000.00	\$ 48.00	\$ 12,000.00
16	604	2	Each	Manholes Adjusted to Grade	\$ 275.00	\$ 550.00	\$ 700.00	\$ 1,400.00
17	Spec.	1	Each	Formed Construction Joint (1 @ 20 L.F.)	\$ 100.00	\$ 100.00	\$ 360.00	\$ 360.00
First Street Length: 770 L.F. or 0.15 miles Width: 18' (1,620 S.Y. including driveway/mailbox approaches and radius work) Type: 448 Surface Course								
18	407	85	Gal	Bituminous Tack Coat Applied to Existing Pavement at Rate of 0.05 Gallons Per Square Yard	\$ 3.00	\$ 255.00	\$ 2.00	\$ 170.00
19	448	70	CY	Asphalt Concrete Surface Course, PG 64-22, Type 1M Applied, Spread and Compacted at the Average Depth of 1 1/2"	\$ 138.00	\$ 9,660.00	\$ 125.00	\$ 8,750.00
20	Spec.	2	Each	Formed Construction Joint (2 @ 77 L.F.)	\$ 300.00	\$ 600.00	\$ 360.00	\$ 720.00
Miscellaneous								
21	614	Lump Sum		Maintaining Traffic		\$ 2,150.00		\$ 5,000.00
22	624	Lump Sum		Mobilization		\$ 1,500.00		\$ 4,000.00
23	103.05	Lump Sum		Premiums on Industrial Insurance and Performance Bond		\$ 2,000.00		\$ 1,500.00
<b>TOTAL AMOUNT BID</b>						<b>\$ 178,954.25</b>		<b>\$ 189,632.50</b>