

**Henry County Engineer  
2012 Flatrock Township Improvements  
Bid Tab - Opening August 9, 2012**

**Road M from Road 17C to Road 17D**

Length: 3565 L.F. or 0.68 miles

Width: 16 (Approx. 6,374 S.Y. including driveway/approach and radius work)

Type: ODOT Spec 254 and 448 Mill and Surface Course w/ 617 Berm placed and compacted an average of 1.5' wide on each side

Ref. #	Item	Quantity	Unit	Description	Engineer's Estimate		Gerken Paving	
					Unit Price	Total Price	Unit Price	Total Price
1	254	6,375	S.Y.	Pavement Planning	\$ 2.10	\$ 13,387.50	\$ 1.10	\$ 7,012.50
2	407	320	Gal	Bituminous Tack Coat applied at 0.05 gallons per square yard	\$ 2.80	\$ 896.00	\$ 1.90	\$ 608.00
3	448	266	C.Y.	Asphalt concrete surface course PG 64-22, Type 1M applied, spread and compacted at the average depth of 1 1/2 inches	\$ 165.00	\$ 43,890.00	\$ 138.00	\$ 36,708.00
4	617	99	C.Y.	Stabilized crushed aggregate berm in place and compactd at the average depth of 3"	\$ 55.00	\$ 5,445.00	\$ 39.00	\$ 3,861.00
5	Spec.	2	EA	Formed Construction Joint ( 76 L.F.)	\$1,500.00	\$ 3,000.00	\$ 200.00	\$ 400.00
6	614	1	L.S.	Maintaining Traffic	\$1,200.00	\$ 1,200.00	\$ 750.00	\$ 750.00
7	624	1	L.S.	Mobilization	\$1,531.00	\$ 1,531.00	\$ 1,000.00	\$ 1,000.00
8	103.05	1	L.S.	Contract Performance & Payment Bond	\$ 438.00	\$ 438.00	\$ 325.00	\$ 325.00
<b>Total Bid</b>					<b>\$ 56,400.00</b>		<b>\$ 50,664.50</b>	