

**LEGAL NOTICE
NOTICE TO CONTRACTORS**

Sealed proposals will be received at the Township Building for Pleasant Township, Fiscal Officer, Tyler Thomas, 327 Railway Avenue (PO Box 463), Holgate Ohio 43527, until Monday, July 17th, 2023 at 7:00 P.M. for the improvement of the following Township roads:

- Pleasant Township- Road A from Road 15 to Road 16 (includes Putnam County) to be resurfaced including berm.**
- Pleasant Township- Road 15 from Road 16C to Road D1 to be resurfaced including berm.**
- Pleasant Township- Road F from SR 108 to Road 16C to be resurfaced including berm.**
- Flatrock Township- Road 16 from Road K to Road Z to be resurfaced including berm.**
- Napoleon Township- Road O (O6) from Road 17 to Road 19 to be resurfaced including berm.**
- Napoleon Township- Road 17 from Road M1 to Road N to be resurfaced including pavement repairs (will be marked out prior to start) and berm.**
- Napoleon Township- Road Q1 crossover just West of Road 17.**
- Napoleon Township- Maintenance Building asphalt addition area with alternate concrete slab.**

Pleasant Township, Henry County, Ohio, in accordance with estimates and specifications on file with the Pleasant Township Fiscal Officer.

Bidding documents are available online at www.henrycountyengineer.com

Bids are to be submitted on a unit price basis.

The contracts will be awarded to the lowest, competent and responsible bidder.

Each bidder is required to file with his bid a bid guaranty in the form of either:

1. A bond for the full amount of the bid; or
2. A certified check, cashier's check or letter of credit pursuant to Chapter 1305 of the Ohio Revised Code, in the amount of ten (10%) percent of the bid price as guarantee that, if the contract be awarded on such bid, the bidder will enter into a contract and the performance of it will be properly secured.

The successful bidder, if using a (10%) bid guaranty, shall be required to provide a contract performance and payment bond for the full amount of the bid.

Estimated cost of the improvements is:	Resurfacing:	\$754,575.00
	Alternate (Concrete Slab):	\$751,060.00

Prevailing Wage Rates per Section 4115 of the Ohio Revised Code shall prevail on this project.

The Board of Trustees reserves the right to award separate contracts for the above noted improvements. The Board of Trustees reserves the right to reject any or all bids.

BY ORDER OF
THE BOARD OF TRUSTEES
PLEASANT TOWNSHIP
HENRY COUNTY, OHIO

Tyler Thomas, Fiscal Officer
PO Box 463
Holgate OH 43527

ROAD BIDDING BLANK

To: Board of Trustees
 Pleasant Township- Resurface Project
 Henry County, Ohio

7.17.23

Road A between 15 and 16 (includes Putnam County)
 Length: 5630 Feet or 1.07 Mile(s)
 Width: 11.5 Feet (Approx. 7240 S.Y. including radius and driveway work)
 Type: ODOT Spec 823 W/ 617 Berm @ 1.5 Feet Wide Each Side

<u>Ref. #</u>	<u>Item</u>	<u>Quantity</u>	<u>Unit</u>	<u>Description</u>	<u>Unit Price</u>	<u>Total Price</u>
1	407	720	Gal	Bituminous Tack Coat applied at 0.05 gallons per square yard	\$ _____	\$ _____
2	823	101	C.Y.	Asphalt intermediate course PG 64-22, Type 1 (823) applied, spread and compacted at the average depth of 0.5 inches	\$ _____	\$ _____
3	823	252	C.Y.	Asphalt concrete surface course PG 64-22, Type 1 (823) applied, spread and compacted at the average depth of 1.25 inches	\$ _____	\$ _____
4	617	105	C.Y.	Stabilized crushed aggregate berm in place and compacted at the average depth of 2 inches	\$ _____	\$ _____
5	254	65	S.Y.	Pavement Planing (20' milled including radius)	\$ _____	\$ _____
6	614	1	L.S.	Maintaining Traffic	\$ _____	\$ _____
7	624	1	L.S.	Mobilization	\$ _____	\$ _____
8	103.05	1	L.S.	Contract Performance & Payment Bond	\$ _____	\$ _____
Total Bid						\$ _____

ROAD BIDDING BLANK

To: Board of Trustees
 Pleasant Township- Resurface
 Project
 Henry County, Ohio

7.17.23

Road 15 between 16C and D1
 Length: 4470 Feet or 0.85 Mile(s)
 Width: 18.5 Feet (Approx. 9250 S.Y. including radius and driveway work)
 Type: ODOT Spec 823 W/ 617 Berm @ 1.5 Feet Wide Each Side

<u>Ref. #</u>	<u>Item</u>	<u>Quantity</u>	<u>Unit</u>	<u>Description</u>	<u>Unit Price</u>	<u>Total Price</u>
1	407	930	Gal	Bituminous Tack Coat applied at 0.05 gallons per square yard	\$ _____	\$ _____
2	823	129	C.Y.	Asphalt intermediate course PG 64-22, Type 1 (823) applied, spread and compacted at the average depth of 0.5 inches	\$ _____	\$ _____
3	823	322	C.Y.	Asphalt concrete surface course PG 64-22, Type 1 (823) applied, spread and compacted at the average depth of 1.25 inches	\$ _____	\$ _____
4	617	83	C.Y.	Stabilized crushed aggregate berm in place and compacted at the average depth of 2 inches	\$ _____	\$ _____
5	254	195	S.Y.	Pavement Planing (20' milled including radius)	\$ _____	\$ _____
6	614	1	L.S.	Maintaining Traffic	\$ _____	\$ _____
7	624	1	L.S.	Mobilization	\$ _____	\$ _____
8	103.05	1	L.S.	Contract Performance & Payment Bond	\$ _____	\$ _____
Total Bid						\$ _____

ROAD BIDDING BLANK

To: Board of Trustees
 Pleasant Township- Resurface
 Project
 Henry County, Ohio

7.17.23

Road F between SR 108 and 16C
 Length: 3670 Feet or 0.7 Mile(s)
 Width: 16 Feet (Approx. 6575 S.Y. including radius and driveway work)
 Type: ODOT Spec 823 W/ 617 Berm @ 1.5 Feet Wide Each Side

<u>Ref. #</u>	<u>Item</u>	<u>Quantity</u>	<u>Unit</u>	<u>Description</u>	<u>Unit Price</u>	<u>Total Price</u>
1	407	660	Gal	Bituminous Tack Coat applied at 0.05 gallons per square yard	\$ _____	\$ _____
2	823	92	C.Y.	Asphalt intermediate course PG 64-22, Type 1 (823) applied, spread and compacted at the average depth of 0.5 inches	\$ _____	\$ _____
3	823	229	C.Y.	Asphalt concrete surface course PG 64-22, Type 1 (823) applied, spread and compacted at the average depth of 1.25 inches	\$ _____	\$ _____
4	617	68	C.Y.	Stabilized crushed aggregate berm in place and compacted at the average depth of 2 inches	\$ _____	\$ _____
5	254	70	S.Y.	Pavement Planing (20' milled including radius)	\$ _____	\$ _____
6	614	1	L.S.	Maintaining Traffic	\$ _____	\$ _____
7	624	1	L.S.	Mobilization	\$ _____	\$ _____
8	103.05	1	L.S.	Contract Performance & Payment Bond	\$ _____	\$ _____
Total Bid						\$ _____

ROAD BIDDING BLANK

To: Board of Trustees
 Flatrock Township
 Henry County, Ohio

7.17.23

Road 16 between Road K and
 Road Z

Length: 4570 Feet or 0.87 Mile(s)

Width: 15.5 Feet (Approx. 7925 S.Y. including radius and driveway work)

Type: ODOT Spec 823 W/ 617 Berm @ 1.5 Feet Wide Each Side

<u>Ref. #</u>	<u>Item</u>	<u>Quantity</u>	<u>Unit</u>	<u>Description</u>	<u>Unit Price</u>	<u>Total Price</u>
1	407	790	Gal	Bituminous Tack Coat applied at 0.05 gallons per square yard	\$ _____	\$ _____
2	823	110	C.Y.	Asphalt intermediate course PG 64-22, Type 1 (823) applied, spread and compacted at the average depth of 0.5 inches	\$ _____	\$ _____
3	823	276	C.Y.	Asphalt concrete surface course PG 64-22, Type 1 (823) applied, spread and compacted at the average depth of 1.25 inches	\$ _____	\$ _____
4	617	85	C.Y.	Stabilized crushed aggregate berm in place and compacted at the average depth of 2 inches	\$ _____	\$ _____
5	245	160	S.Y.	Pavement Planing (20' milled including radius)	\$ _____	\$ _____
6	614	1	L.S.	Maintaining Traffic	\$ _____	\$ _____
7	624	1	L.S.	Mobilization	\$ _____	\$ _____
8	103.05	1	L.S.	Contract Performance & Payment Bond	\$ _____	\$ _____
Total Bid						\$ _____

ROAD BIDDING BLANK

To: Board of Trustees
 Napoleon Township
 Henry County, Ohio

7.17.23

Road O6 (O) between Road 17 and
 19
 Length: 10920 Feet or 2.07 Mile(s)
 Width: 18.75 Feet (Approx. 22880 S.Y. including radius and driveway work)
 Type: ODOT Spec 823 W/ 617 Berm @ 1.5 Feet Wide Each Side

<u>Ref. #</u>	<u>Item</u>	<u>Quantity</u>	<u>Unit</u>	<u>Description</u>	<u>Unit Price</u>	<u>Total Price</u>
1	407	2,290	Gal	Bituminous Tack Coat applied at 0.05 gallons per square yard	\$ _____	\$ _____
2	823	318	C.Y.	Asphalt intermediate course PG 64-22, Type 1 (823) applied, spread and compacted at the average depth of 0.5 inches	\$ _____	\$ _____
3	823	795	C.Y.	Asphalt concrete surface course PG 64-22, Type 1 (823) applied, spread and compacted at the average depth of 1.25 inches	\$ _____	\$ _____
4	617	203	C.Y.	Stabilized crushed aggregate berm in place and compacted at the average depth of 2 inches	\$ _____	\$ _____
5	245	150	S.Y.	Pavement Planing (20' milled including radius)	\$ _____	\$ _____
6	614	1	L.S.	Maintaining Traffic	\$ _____	\$ _____
7	624	1	L.S.	Mobilization	\$ _____	\$ _____
8	103.05	1	L.S.	Contract Performance & Payment Bond	\$ _____	\$ _____
Total Bid						\$ _____

ROAD BIDDING BLANK

To: Board of Trustees
Napoleon Township
Henry County, Ohio

7.17.23

Crossover- Q1 west of Road 17
Length: 15 Feet or 0 Mile(s)
Width: 18 Feet (Approx. 30 S.Y. including radius and driveway work)
Type: ODOT Spec 823

<u>Ref. #</u>	<u>Item</u>	<u>Quantity</u>	<u>Unit</u>	<u>Description</u>	<u>Unit Price</u>	<u>Total Price</u>
1	823	2	C.Y.	Asphalt concrete surface course PG 64-22, Type 1 (823) applied, spread and compacted at the average depth of 1.5 inches	\$ _____	\$ _____
2	245	25	S.Y.	Pavement Planing (20' milled including radius)	\$ _____	\$ _____
3	614	1	L.S.	Maintaining Traffic	\$ _____	\$ _____
4	624	1	L.S.	Mobilization	\$ _____	\$ _____
5	103.05	1	L.S.	Contract Performance & Payment Bond	\$ _____	\$ _____
Total Bid						\$ _____

ROAD BIDDING BLANK

To: Board of Trustees
 Napoleon Township
 Henry County, Ohio

7.17.23

Road 17 between Road M1 and Road N
 Length: 4390 Feet or 0.83 Mile(s)
 Width: 16 Feet (Approximately 7880 SY including radius and driveway work)
 Type: ODOT Spec 823 with 301 base material including berm at 1.5 feet wide each side

<u>Ref. #</u>	<u>Item</u>	<u>Quantity</u>	<u>Unit</u>	<u>Description</u>	<u>Unit Price</u>	<u>Total Price</u>
1	203	33	CY	Excavation 4" depth with material hauled off (Various Pavement Repairs marked out along edge)	\$ _____	\$ _____
2	204	300	SY	Subgrade Compaction	\$ _____	\$ _____
3	301	33	CY	Bituminous Aggregate Base, (4" average compacted depth, includes 407 tack coat on vertical face)	\$ _____	\$ _____
4	407	395	Gal	Bituminous Tack Coat applied at 0.05 gallons per square yard	\$ _____	\$ _____
5	823	328	C.Y.	Asphalt concrete surface course PG 64-22, Type 1 (823) applied, spread and compacted at the average depth of 1.5 inches	\$ _____	\$ _____
6	617	82	CY	Stabilized crushed aggregate berm in place and compacted at the average depth of 2 inches	\$ _____	\$ _____
7	254	200	S.Y.	Pavement Planing (20' milled including radius)	\$ _____	\$ _____
8	614	1	L.S.	Maintaining Traffic	\$ _____	\$ _____
9	624	1	L.S.	Mobilization	\$ _____	\$ _____
10	103.05	1	L.S.	Contract Performance & Payment Bond	\$ _____	\$ _____
Total Bid						\$ _____

ROAD BIDDING BLANK

Township Maintenance Building

Length: Varies

Width: Varies (Approx. 280 S.Y.)

Type: ODOT Spec 823, with Spec 301 base material

7.17.23

Asphalt

<u>Ref. #</u>	<u>Item</u>	<u>Quantity</u>	<u>Unit</u>	<u>Description</u>	<u>Unit Price</u>	<u>Total Price</u>
1	203	93	CY	Excavation of 12" of marked area (includes removing existing drive and haul off, sod dirt can be redistributed on property in low areas)	\$ _____	\$ _____
2	204	280	SY	Subgrade Compaction	\$ _____	\$ _____
3	304	62	CY	Aggregate base compacted (8")	\$ _____	\$ _____
4	301	18	CY	Bituminous Aggregate Base, (2.5 inches average compacted depth, includes 407 tack coat on vertical face)	\$ _____	\$ _____
5	407	14	Gal	Bituminous Tack Coat applied at 0.05 gallons per square yard	\$ _____	\$ _____
6	823	11	C.Y.	Asphalt concrete surface course PG 64-22, Type 1 (823) applied, spread and compacted at the average depth of 1.5 inches	\$ _____	\$ _____
7	624	1	L.S.	Mobilization	\$ _____	\$ _____
8	103.05	1	L.S.	Contract Performance & Payment Bond	\$ _____	\$ _____
9	CONC	18	SY	Reinforced cement concrete approach in front of overhead doors, Class C Type Concrete (approximately 4'X40' at 6 inches thick) with #4 rebar at 12" each way	\$ _____	\$ _____
10	209	1	L.S.	Grading of excess dirt and sod	\$ _____	\$ _____
11	659	30	S.Y.	Seeding and Mulching	\$ _____	\$ _____
Total Bid					\$ _____	

Alternate- Concrete Slab

Alternate: Concrete Pad

<u>Ref. #</u>	<u>Item</u>	<u>Quantity</u>	<u>Unit</u>	<u>Description</u>	<u>Unit Price</u>	<u>Total Price</u>
1	202	1	LS	Saw cut joints in existing asphalt to prepare for concrete- 2 places (40 LF Total)	\$ _____	\$ _____
2	203	34	CY	Excavation of dirt and existing asphalt drive 12 inches deep (22.5'X 40.5', approximately 880 sf, existing drive haul off, sod dirt can be redistributed on property in low areas)	\$ _____	\$ _____
3	204	101	SY	Subgrade Compaction	\$ _____	\$ _____
4	304	17	CY	Aggregate base compacted (6")	\$ _____	\$ _____
5	624	1	LS	Mobilization	\$ _____	\$ _____
6	103.05	1	LS	Contract Performance & Payment Bond	\$ _____	\$ _____
7	CONC	97	SY	Reinforced cement concrete slab in front of overhead doors, Class C Type Concrete (approximately 22'X40' at 6 inches thick) with #4 rebar at 12" each way	\$ _____	\$ _____
8	209	1	LS	Grading of excess dirt and sod	\$ _____	\$ _____
9	659	30	SY	Seeding and Mulching	\$ _____	\$ _____
Total Bid					\$ _____	

TOTAL BID with ASPHALT AT MAINTENANCE BLD: \$ _____

TOTAL BID with CONCRETE SLAB AT MAINTENANCE BLD: \$ _____

Road Bid Blank Continued

Date of Sale: Monday July 17th, 2023 at 7:00 P.M.

Paving of Various Roads

All work and material contracted for seal coating shall meet the requirements of the 1997 State of Ohio, Department of Transportation, Construction and Material Specifications. All other work shall meet the requirements of the State of Ohio, Department of Transportation, Construction and Material Specifications in effect on the date of sale, together with any modifications to the same stated herein. **This includes removing grass and other debris from the road surface.**

Spreading and placement of asphalt shall be done with full width paving equipment.

Unless otherwise noted one (1") inch average depth "formed" construction joint as directed by the Township Trustee shall be constructed at all pavement termini locations and at all interruptions to the continuous placement of 823 material (weather, end of day, etc.) A separate bid item has been included for "pavement planning" at the pavement termini locations on all projects. All construction joint locations will be field painted prior to bidding. Approximate length of pavement planning is 20 feet and to include the radius unless otherwise directed by the Township Trustees.

The asphalt binder grade for all asphalt concrete specified shall be PG 64-22.

Aggregate used in the asphalt concrete mix and for seal coating shall be State approved quarry run mineral aggregate.

Cut back asphalt may be used on applicable bid items between the period of October 15th and April 15th.

There are no restricted construction dates for the use of cut backs for penetration prime coat, maintenance mix or dust control.

Prevailing Wage Rates per Section 4115 of the Ohio Revised Code shall prevail on this project. A copy of the applicable wage rates may be obtained from the State of Ohio Wage and Hour Division via the internet at the following web site:

<http://www.com.ohio.gov/laws>

Should the bidder not have access to the internet, a complete set of the applicable wage rates are available at the office of the Henry County Engineer. A copy will be provided if requested.

Contractors are required to furnish the Township with a certificate of insurance in the minimum amount of \$1,000,000.00 primary and \$1,000,000.00 umbrella coverage. The Township, its elected office and employees shall be named as additional insured with respect to all activities under any agreement resulting from this bidding. The certificate of insurance shall provide that such insurance shall not be cancelled without thirty (30) days prior written notice to the Township. Contractors will replace certificate for any insurance expiring prior to the effective end date under any agreement resulting from this bidding.

Contractors shall maintain Worker's Compensation coverage as required by Ohio law. A copy of a valid Worker's Compensation certificate shall be submitted with the bid.

The Contractor shall indemnify and hold harmless the Township, its agents and employees from any and all losses, claims, damages, lawsuits, costs, judgments, expenses or any other liabilities which they may incur as a result of bodily injury, sickness, disease or death, or injury to or destruction of tangible property including the loss of use resulting therefrom, caused in whole or part by the negligent act or omission of the Contractor or any person directly or indirectly employed by any of them or any person for whose act any of them may be liable.

Accompanying this proposal is a bid guaranty in the form of either:

- 1) A bond for the full amount of the bid, on the above improvement; or
- 2) A certified check, cashier's check or letter of credit pursuant to Chapter 1305 of the Ohio Revised Code, in the amount of ten percent (10%) of the bid on the above improvements, payable to the order of the Board of Trustees, PLEASANT TOWNSHIP, which check or bond is to be forfeited if, in case this proposal is accepted, the undersigned shall fail to execute a contract within ten (10) days of Notice of Award.

This contract shall be under the direct supervision of the Pleasant Township Trustees and the Henry County Engineer.

All items are approximate, and final measurement of completed items will govern final payment.

In the event of discrepancy between the unit and total price bid, the unit price shall prevail. The unit prices shall remain in effect and held firm for the term of this contract. ODOT Item 401.20 Asphalt Binder price adjustment does not apply.

The Contractor shall be responsible for all construction one (1) year after project completion and acceptance. The Contractor shall make all corrections as necessary by reason of noted defects. The Trustees will give notice of observed defects with reasonable promptness. In the event that the Contractor fails to make repairs, adjustments or complete other work which may be required by such defects, the Trustees may do so and charge the Contractor the costs incurred.

The Board of Trustees reserve the right to award separate contracts on the various roads described. The Board of Trustees further reserves the right to reject any or all bids.

The seal coating and resurfacing shall be completed on or before September 15, 2023.

For each calendar day that any work shall remain uncompleted after the stated completion date the appropriate sum, in accordance with the schedule of liquidated damages per Section 108.07 of the Standard Specifications of the State of Ohio Department of Transportation, will be deducted from any monies due the Contractor, not as a penalty but as liquidated damages; provided however, that due account shall be taken of any adjustment of the completion date granted by the Board of Trustees of Pleasant Township.

A work day will be counted as lost if the Contractor's efficiency is reduced more than fifty (50%) percent on the critical items under construction at that time. Weekends and holidays will not be counted as lost work days.

Submitted By: _____
CONTRACTOR

Address: _____

Signed By: _____
Name/Title

Phone Number

Email Address

Fax Number