

COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N R- 8 - E

SECTION: 1

8/22/79 R.W., J.J., C.S.

C - Found Pk in bridge deck established by Wood County Engineer (see Wood Co. plans for bridge #10, Rd 7D). Removed Pk and placed boat spike in bridge deck. Pk's 6' north and west. Boat spike is 12' north of south edge 24' deck.

- 34.24' W.N.W. to "+" NW bridge abutment. (P)
- 34.24' N.E. to "+" NE bridge abutment. (P)
- 34.19' S.E. to "+" SE bridge abutment. (P)
- 34.08' W.S.W. to "+" SW bridge abutment. (P)

7/13/88 R.W., S.K., K.A.

- 34.22' W.N.W. to "+" NW bridge abutment. (P)
- 34.21' N.E. to "+" NE bridge abutment. (P)
- 34.17' S.E. to "+" SE bridge abutment. (P)
- 34.05' S.W. to "+" SW bridge abutment. (P)


9/6/79 R.W., J.J., C.S.

D - Found iron pin in clay tile over high point of stone (4"x8"x20") 17" below road surface. Removed iron pin. Placed center punched RR spike on surface over high point of stone. Pk's 6' northeast and southeast. Stone is on west edge 18' pavement.

- 53.91' S.S.W. to duplex nw/s power pole.
- 22.89' W. to "+" chiseled in top end 12" CMP.

7/13/88 R.W., S.K., K.A.

- 44.13' S.W. to "+" SE corner catch basin. (P)
- 53.75' S.S.W. to duplex nw/s power pole.
- 22.77' W. to "+" east end CMP. (P)



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N R- 8 - E

SECTION: 1

9/25/75 J.G., B.B., R.S.

A - Found vertical tile over top of stone. Stone was 9" deep. Also found stone 24" deep. Top stone was removed because it was broken. Placed #4 rebar over stone. Pk's 6' north and east. (All meas. are horz.)

49.60' W.N.W. to duplex sw/s telephone pole.

41.49' S.E. to center anchor bolt eye bar connection, 84" pipe.

28.85' S.W. to SE corner conc. bridge rail.

19.00' S.W. to NE corner conc. bridge rail.

7/13/88 R.W., S.K., K.A.

49.60' W.N.W. to duplex s/s buried cable marker.

43.92' E.S.E. to "+" east end conc. pipe. (P)

28.90' S.S.W. to SE corner conc. banister.

8/21/79 R.W., J.J., C.S.

B - Found recorded iron pipe 0.13' south of top center of stone (5"x8"x7") 14" below road surface. Removed iron pin. Placed center punched RR spike on surface over top center of stone. Pk's 6' north and west. Stone is fractured in two pieces. Stone is 3.4' north of south edge 11' pavement.

18.07' N.N.W. to "+" top east end conc. headwall.

30.44' S. to duplex w/s wood corner post.

39.06' S.W. to duplex n/s clump of buckeye trees.

7/13/88 R.W., S.K., K.A.

68.28' W.N.W. to "+" center east wing of catch basin. (P)


18.11' N.N.W. to "+" east end conc. headwall. (P)

14.03' N.E. to 5/8" iron pin 2' north of pavement.

16.60' S.W. to "+" south end cast iron pipe. (P)

30.38' S. to duplex w/s wood corner post.

38.99' S.W. to duplex n/s clump of buckeye trees.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N R- 8 - E

SECTION: 2

8/21/79 R.W., J.J., C.S.

C - Found stone (6"x11"x22") 12" below road surface. Top of stone is loose and sits on base of stone. Placed center punched RR spike on surface and on the South Line of Sec. 35; Damascus Twp. at the intersection with the North-South ¼ Section Line, Sec. 2; Richfield Twp. High point of stone is 0.23' north of RR spike. Pk's 6' northwest and northeast. Stone is 0.4' south of south edge pavement.

- 35.15' N.E. to duplex se/s 42' walnut.
- 17.25' S.E. to "+" SW corner stone headwall. (P)
- 36.80' S.S.E. to duplex nw/s power pole.
- 29.40' S. to near face 3" iron pine. NO GOOD
- 11.91' E. to S¼ Post, Sec. 35; Damascus Twp.

7/13/88 R.W., S.K., K.A.

- 27.97' N.N.E. to "+" west end conc. headwall. (P)
- 17.22' S.E. to "+" west end stone headwall. (P)
- 36.60' S.S.E. to duplex nw/s power pole.


5/16/83 R.W., D.B., J.B.

D - Found stone (4"x7"x14") 8" below road surface. Placed center punched RR spike on surface over stone. Pk's 6' north and east. Stone is 5' east of west edge pavement.

- 30.86' W.N.W. to Pk in alum. drainage pipe. (P)
- 36.38' W.S.W. to Pk in alum. drainage pipe. (P)

7/13/88 R.W., S.K., K.A.

- 30.84' N.W. to Pk nail in aluminum pipe. (P)
- 15.11' N.E. to 5/8" iron pin 1' east of pavement.
- 14.81' S.E. to 5/8" iron pin 1' east of pavement.
- 36.37' S.W. to Pk nail in aluminum pipe. (P)



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N R- 8 - E

SECTION: 2


10/2/75 J.G., R.S., B.B., T.F.

A - Found stone 13" deep. Also found smaller stone 8" west of true corner and evidence of a hub south of stone. Placed RR spike over stone. Pk's 6' north and west.
 27.38' S.E. to "+" east end 48" RCP.
 38.38' S.W. to "+" west end 48" RCP.

7/13/88 R.W., S.K., K.A.
 66.40' E.N.E. to center USGS Bench Mark. (P)
 38.38' S.E. to "+" east end conc. pipe. (P)
 39.91' S.E. to duplex sw/s power pole.
 27.35' S.W. to "+" west end conc. pipe. (P)
 32.34' E. to Damascus Twp. corner.

10/2/75 J.G., R.S., B.B., T.F.
 B - Found stone 9" deep. Placed RR spike over same. Stone is 9" north of south edge pavement. Pk's 6' north and west.
 34.94' N.W. to duplex ne/s telephone pole.
 149.26' N.E. to duplex s/s telephone pole. GONE
 114.43' S.E. to duplex n/s power pole.
 24.70' E. to Damascus Twp. stone.

7/13/88 R.W., S.K., K.A.
 35.05' N.W. to duplex ne/s buried cable marker.
 17.03' N.E. to 5/8" iron pin 3' north of pavement.
 11.79' E.S.E. to 5/8" iron pin 3' south of pavement.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N R- 8 - E

SECTION: 2

5/16/83 R.W., D.B., J.B.

E - Found stone (4"x12"x16") 8" below road surface. Placed center punched RR spike on surface over top center of stone. Pk's 6' north and west. Stone is 7.0' west of east edge pavement.

54.30' S.W. to "+" north end CMP. (P)

34.98' W.S.W. to "+" south end conc. block headwall. (P)

34.48' W.N.W. to "+" north end conc. block headwall. (P)

Note: Removed RR spike established 9/6/79.

7/13/88 R.W., S.K., K.A.


34.48' W.N.W. to "+" north end conc. block headwall. (P)

14.56' N.E. to 5/8" iron pin 1' east of pavement.

11.76' S.E. to 5/8" iron pin 1' east of pavement.

54.26' S.S.W. to Pk nail north end CMP. (P)

34.99' W.S.W. to "+" south end conc. block headwall. (P)



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N R- 8 - E

SECTION: 3

8/1/79 R.W., J.J., G.M.

A - Found recorded RR spike in iron pipe over iron pin on n/s of top stone. Top stone was 0.25' north and 0.42' west of top center of true stone (6"x6"x20") 22" below road surface. Removed RR spike, iron pipe, iron pin, and top stone. Placed center punched RR spike on surface over top center of stone. Pk's 6' north and east. Stone is 8.2' west of west edge pavement.

64.52' N. to "+" SE corner catch basin. (P)

69.15' E.N.E. to center USGS bench mark "W-116 1947". (P)

38.74' S.E. to SW corner bridge rail.

9.94' S.S.W. to "+" in conc. wingwall. (P)

14.78' S.W. to "+" in west end conc. wingwall.

28.79' E. to SW Corner, Sec. 34: Damascus Twp.

7/13/88 R.W., S.K., K.A.

Found nail/shiner and Pk's north and east.

64.52' N. to "+" SE corner catch basin. (P)

69.14' E.N.E. to center USGS bench mark "W-116 1947".(P)

37.98' E.S.E. to "+" north end NE wingwall. (P)

9.93' S.S.W. to "+" in top of conc. wingwall. (P)

14.80' S.W. to "+" west end conc. wingwall. (P)

A	B
C	

COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N R- 8 - E

SECTION: 3

8/20/79 R.W., J.J., C.S.

B - Found stone (6'x6"x15") 20" below road surface. Placed center punched RR spike on surface over high point of stone. Pk's 6' northeast and northwest. Stone is 0.6' north of south edge 12' pavement.

38.89' N.N.E. to "+" in large stone (15"x15"x15"). (P)

73.12' N.E. to duplex w/s buried cable marker.

60.82' E.S.E. to near face Twp. Rd. sign post. GONE

32.56' S.S.E. to duplex n/s power pole.

30.87' E. to S $\frac{1}{4}$ Post, Sec. 34; Richfield Twp.

7/13/88 R.W., S.K., K.A.

18.41' N.W. to 5/8" iron pin 3' north of pavement.

38.86' N.N.E. to "+" in large stone (15"x15"x15"). (P)

73.25' N.E. to duplex w/s buried cable marker.

32.96' S.S.E. to duplex (new) w/s power pole.

8/1/79 R.W., J.J., G.M.

C - Found recorded iron pipe over small stone 0.63' west of high point of true stone (4"x7"x16") 16" below road surface. Found iron pipe on s/s of small stone. Removed iron pipes and small stone. Placed center punched RR spike on surface over high point of stone. Pk's 6' northeast and southeast. Stone is 0.6' west of west edge 18' pavement.

30.59' W. to center conc. R/W monument. (P)

56.28' N.W. to duplex e/s telephone pole.

33.25' N.E. to "+" south end, east wall catch basin. (P)

30.46' E.N.E. to shiner w/s power pole.

29.92' E. to center conc. R/W monument. (P)


7/13/88 R.W., S.K., K.A.

Found nail/shiner and Pk's northeast and southeast.

33.30' N.E. to "+" south end east wall of catch basin. (P)

30.47' E.N.E. to nail/shiner w/s power pole.

26.93' S.E. to 5/8" iron pin at east edge pavement.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N R- 8 - E

SECTION: 4


8/14/79 R.W., G.M.

A - Found stone (11"x12"x19") 16" below road surface. Also found stone over said stone. Removed top stone. Placed center punched RR spike on South Line of Sec. 32; Damascus Twp. at intersection with West Line of Sec. 4; Richfield Twp. RR spike is 1.0' south of high point of stone. Pk's 6' north and west. Stone is 1' south of south edge 18' pavement.

- 29.97' N.N.W. to SE corner conc. anchor post.
- 33.80' N.N.W. to duplex e/s power pole.
- 20.01' E.S.E. to "+" in conc. wingwall.
- 35.92' S.S.W. to "+" in conc. wingwall. (P)
- 51.77' W.S.W. to NE corner anchor post.
- 57.94' W.S.W. to duplex n/s power pole.
- 52.32' E. to SW corner, Sec. 33; Damascus Twp.

7/13/88 R.W., S.K., K.A.

- 32.56' N.W. to center USGS BM "V116 1947". (P)
- 33.80' N.N.W. to duplex e/s power pole.
- 19.99' E.S.E. to "+" in bridge wing.
- 35.93' S.S.W. to "+" in bridge wing.
- 57.94' S.W. to duplex n/s power pole.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N R- 8 - E

SECTION: 4

8/20/79 R.W., J.J., C.S.

B - Found stone (7"x12"x10") 16" below road surface. Placed center punched RR spike on surface over top center of stone which is on the South Line of Sec. 33, Damascus Twp. Pk's 6' north and west.

36.44' N.N.W. to center USCG Sta. "STONER-1947". (P)

50.64' N.E. to SW corner anchor post.

48.70' S.S.E. to duplex n/s power pole.

43.46' S.S.W. to "+" chiseled in 1" sq. iron bar in center conc. anchor post. (P)

40.93' E. to S $\frac{1}{4}$ Post, Sec. 33, Damascus Twp.

7/13/88 R.W., S.K., K.A.

36.44' N.W. to center USCG Sta. "STONER-1947". (P)

50.58' N.E. to saw cut at SW corner conc. monument.

48.66' S.S.E. to duplex n/s power pole.

43.47' S.S.W. to "+" chiseled in 1" sq. bar in conc. (P)

5/13/83 R.W., D.B., J.B.

C - Found stone (8"x10"x12") 13" below road surface. Placed center punched RR spike on surface over stone. Pk's 6' north and east. Stone is 4.8' east of west edge pavement.

20.86' E.N.E. to duplex n/s power pole.


102.07' S.S.E. to center USGS Sta. "CRONINGER-1950". (P)

7/13/88 R.W., S.K., K.A.

7.25' N.W. to 5/8" iron pin 1' west of pavement.

18.53' N.E. to 5/8" iron pin 1' east of pavement.

102.13' S.S.E. to center USGS Sta. "CRONINGER-1950". (P)



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N R- 8 - E

SECTION: 4

5/12/83 R.W., D.B., J.B.

D - Found stone (5"x10"x15") 13" below road surface. Placed center punched RR spike on surface over stone. Pk's 6' north and east. Stone is 2.0' east of west edge pavement.

112.16' N.N.E. to duplex w/s power pole.

25.87' E. to USGS Sta. "LONG-1950".


37.29' S.E. to duplex se/s power pole.

7/13/88 R.W., S.K., K.A.

21.51' N.E. to 5/8" iron pin 1' east of pavement.

25.91' E. to center USGS Sta. "LONG-1950".

21.98' S.E. to 5/8" iron pin 1' east of pavement.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N R- 8 - E

SECTION: 5

8/9/79 R.W., J.J., G.M.

A - Found recorded iron pipe over round stone over top center of true stone (10"x11"x12") 22" below road surface. Removed iron pipe and round stone. Placed center punched RR spike on surface over top center of stone. Pk's 6' north and west. RR spike is on the South Line of Sec. 31, Damascus Twp. Stone is 6.9' north of south edge 13' pavement.

43.66' W.N.W. to duplex s/s telephone pole. NO GOOD

95.72' E.N.E. to duplex sw/s telephone pole.

59.81' S.S.E. to duplex nw/s power pole.

37.42' S.S.W. to "+" west end 66" RCP.

57.52' E. to SE corner, Sec. 31, Damascus Twp.

7/13/88 R.W., S.K., K.A.


45.23' N.W. to duplex s/s telephone pole. (NEW)

95.82' E.N.E. to duplex sw/s telephone pole.

67.38' S.E. to center USGS Sta. "BARNES 1963".

59.79' S.E. to duplex nw/s power pole.

37.42' S.W. to "+" west end conc. pipe. (P)



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N R- 8 - E

SECTION: 5

8/15/79 R.W., J.J., G.M.

B - Found stone (6"x12"x17") 12" below road surface. Also found wood stake and a fractured stone. Removed stake and fractured stone. Placed center punched RR spike on the South Line, Sec. 32, Damascus Twp. at the intersection with the North-South ¼ Sec. Line, Sec. 5, Richfield Twp. Top center of stone is 0.29' south of RR spike. Pk's 6' north and west. Stone is 6.8' north of south edge 13' pavement.

65.10' W.N.W. to duplex s/s telephone pole (leans north).

28.38' N.E. to SW corner conc. catch basin. (P)

84.80' E.N.E. to shiner sw/s telephone pole.

53.20' S.S.E. to duplex n/s 15" locust.

32.32' S.S.W. to "+" SE conc. bridge wingwall. (P)

29.08' S.W. to "+" NW conc. bridge wingwall.

58.59' E. to S¼ Post, Sec. 32, Richfield Twp.

7/13/88 R.W., S.K., K.A.

28.35' N.E. to "+" SW corner catch basin. (P)

32.34' S.S.W. to "+" SE bridge wing. (P)

29.11' S.W. to "+" NW bridge wing. (P)

8/28/79 R.W., J.J., C.S.

C - Found possible cornerstone laying on ditch bank near recent excavation for 15" CMP crossover. Reestablished W¼ Post by single proportionate measurement along the West Line, Sec. 5, Richfield Twp. between the NW corner and SW corner. Placed 5/8" x 30" iron pin at W¼ Post. Top of iron pin is 0.9' below edge of pavement and 3.8' west of west edge pavement. Pk's 10' northeast and southeast.

11.97' W. to "+" chiseled in west end 15" CMP. (P)

33.59' E. to "+" in conc. headwall. (P)

101.98' S.S.E. to duplex e/s buried cable marker. (P)


7/13/88 R.W., S.K., K.A.

25.36' N.E. to 5/8" iron pin at east edge pavement.

33.77' E. to "+" center conc. headwall. (P)

24.44' S.E. to 5/8" iron pin at east edge pavement.

11.81' W. to "+" chiseled in west end CMP. (P)



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4-N R-8-E

SECTION: 6

A - See NE Corner, Section 1, Monroe Twp.

8/13/79 R.W., J.J., G.M.

B - Searched for stone, could not locate. Reestablished N $\frac{1}{4}$ Post on the South Line, Sec. 31, Damascus Twp. by single proportionate measurement between the NW corner and NE corner of Sec. 6, Richfield Twp. Placed center punched RR spike on surface. Pk's 6' north and west. RR spike is 2.6' north of south edge 13' pavement.

113.60' W.N.W. to duplex s/s telephone pole.

23.06' N.N.W. to duplex e/s telephone pole.

18.69' N.E. to "+" conc. bridge wingwall.

13.69' S.E. to "+" conc. bridge wingwall.

33.13' S.S.W. to duplex e/s power pole.

57.50' E. to S $\frac{1}{4}$ Post, Sec. 31, Damascus Twp.


S.K., K.A.

27.84' N.N.E. to "+" west end conc. headwall. (P)

66.38' E.N.E. to "+" east end conc. headwall. (P)

62.82' E.S.E. to "+" east end conc. headwall. (P)

17.61' S.S.E. to "+" west end conc. headwall. (P)



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N R- 8 - E

SECTION: 6


8/23/79 R.W., J.J., C.S.

C - Found recorded iron pin slanted over high point of stone (7"x10"x11"). Removed iron pin and lowered stone to 13" below grade. Placed 5/8" x 12" iron pin over high point of stone. Pk's 6' northwest and southwest. Stone is 3.4' east of east edge pavement.

- 83.17' N.N.W. to 8d nail s/s power pole.
- 131.50' S.S.W. to duplex e/s power pole.
- 76.44' N. to E¼ Post, Sec. 1, Monroe Twp.

7/13/88 R.W., S.K., K.A.

- 83.22' N.N.W. to 8d nail s/s power pole.
- 30.07' S.W. to 5/8" iron pin 2' west of west edge pavement.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4 -N R-8 -E

SECTION: 7

8/23/79 R.W., J.J., C.S.

A - Found iron fence post w/s stone (6"x9"x11") 10" below ditch bank. Placed 1/2" x 18" iron pin on n/s stone with top of iron pin over "+" in top center of stone. Pk's 10' east and 20' southeast. Stone is 9.0' west of west edge 14' pavement.

32.13' N.N.W. to top center hole in SW end 96" CMP.

65.60' N.E. to duplex se/s power pole.

60.81' E.S.E. to duplex sw/s power pole.

73.88' N. to NE corner, Sec. 12, Monroe Twp.

7/14/88 R.W., S.K., K.A.

Stone and iron pin had moved 0.3' down ditch bank. Placed iron pin on the East Line, Sec. 12, Monroe Twp. Iron pin is 0.42' east of "+" in stone.


32.67' N.N.W. to "+" south end CMP. (P)

72.07' N.E. to "+" NE corner catch basin. (P)

65.15' N.E. to nail se/s power pole.

60.68' S.E. to duplex sw/s power pole.

73.88' N. to NE corner, Sec. 12, Monroe Twp.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N R- 8 - E

SECTION: 7

9/7/79 R.W., J.J., C.S.


B - Found recorded iron pin established from road plans. Search for stone was made in 1972, but was not located. Also found Pk's 6' north and west.

- 77.58' N.W. to spike ne/s power pole.
- 34.40' N.N.E. to hole in top north end 60" CMP. (P)
- 140.48' E.N.E. to duplex s/s 36" maple.
- 21.85' S.S.E. to hole in top south end 60" CMP. (P)
- 55.69' S.W. to duplex n/s telephone pole. GONE
- 7/14/88 R.W., S.K., K.A.
- 77.57' N.W. to spike ne/s power pole.
- 34.39' N.N.E. to center hole north end CMP. (P)
- 21.79' S.S.E. to center hole south end CMP. (P)
- 35.48' S.W. to Pk west end CMP. (P)

9/7/79 R.W., J.J., C.S.

C - Searched for stone, could not locate. Reestablished W¼ Post by single proportionate measurement between the SW corner and NW corner, Sec. 7, Richfield Twp. Said point being on the East Line of Sec. 12, Monroe Twp. Placed 5/8" x 30" iron pin. Pk's 10' northeast and southeast. Iron pin is 6.0' west of west edge 16' pavement.

- 62.40' N.N.W. to duplex e/s power pole.
- 67.04' N.N.W. to "+" west end conc. headwall.
- 63.00' N.N.E. to 60d spike w/s power pole. (P)
- 7/14/88 R.W., S.K., K.A.
- 62.51' N.N.W. to duplex e/s telephone pole.
- 67.01' N.N.W. to "+" west end conc. headwall.
- 52.86' N.N.W. to "+" east end conc. headwall. (P)
- 62.98' N.E. to spike w/s power pole. (P)
- 80.07' N. to E¼ Post, Sec. 12, Monroe Twp.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N R- 8 - E

SECTION: 8

8/23/79 R.W., J.J., C.M.

A - Found recorded RR spike 0.22' south of remains of old wooden decayed post. Top is 24" below road surface. Witness ties to bridge and corn crib cross within two tenths of post. Placed RR spike with chiseled "+" over wood post. Pk's 6' north and west. Wood post is 5.4' north of south edge 18' pavement.

20.55' N.W. to SE corner north bridge rail.

75.03' N.N.W. to SW corner corn crib. GONE

42.53' N.E. to duplex s/s buried cable marker.

41.21' S.E. to duplex n/s buried cable marker.

16.50' S.W. to NE corner south bridge rail.


7/14/88 R.W., S.K., K.A.

20.54' N.W. to SE corner bridge banister.

42.52' N.E. to duplex s/s buried cable marker.

41.18' S.E. to duplex n/s buried cable marker.

16.51' S.W. to NE corner bridge banister.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N R- 8 - E

SECTION: 8

8/27/79 R.W., J.J., C.S.

B - Found recorded RR spike 0.10' south of top center of stone (9"x11"x16') 13" below road surface. Placed RR spike with chiseled "+" on surface over top center of stone. Pk's 6' north and west. Stone is 7.5' north of south edge 19' pavement.

40.36' N.W. to duplex sw/s power pole.

33.27' N.N.E. to "+" north end 72" RCP. (P)

44.81' E.S.E. to "+" NE corner catch basin. (P)

36.12' S. to center USGS Sta. "AUSTERMILLER-1947". (P)

23.28' S.S.W. to "+" NW corner catch basin. (P)

7/14/88 R.W., S.K., K.A.

40.33' N.W. to duplex sw/s power pole.

33.28' N.N.E. to "+" north end RCP. (P)

44.81' E.S.E. to "+" NE corner catch basin. (P)

33.32' S.S.E. to "+" south end RCP. (P)

36.10' S. to USGS Sta. "AUSTERMILLER-1947". (P)

23.26' S.S.W. to "+" NW corner catch basin. (P)

9/7/79 R.W., J.J., C.S.

C - Found recorded iron pin on e/s of stone with top angled over top center of stone (8"x10"x23") 7" below grade. Set Pk's 6' northeast and southeast. Stone is 3.0' west of west edge 10' pavement.

17.75' N.W. to "+" top south end conc. headwall. (P)

27.87' N.E. to "+" SE corner conc. catch basin. (P)

28.19' E. to duplex s/s telephone pole.


7/14/88 R.W., S.K., K.A.

38.06' W. to center USGS Sta. "WILLIAM 1947".(P)

17.50' N.W. to "+" south end conc. headwall. (P)

27.94' N.E. to "+" SE corner conc. headwall. (P)

28.33' E. to duplex s/s telephone pole.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N R- 8 - E

SECTION: 9

8/22/79 R.W., J.J., C.S.

A - Found recorded RR spike over top stone over true stone (8"x9"x5") 26" below road surface. Found wood stake on w/s stone. Removed top stone and wood stake. Placed center punched RR spike on surface over top center of stone. Pk's 6' north and west. Stone is 8.5' north of south edge 18' pavement.

37.71' N.W. to center hex bolt stamped "40" in top 96" CMP. (P)

36.85' N.E. to center USGS Sta. "SHIDLER-1947". (P)

32.75' S.E. to "+" top east end, "L" shaped headwall. (P)

38.58' S.W. to center hex bolt stamped "40" in top 96" CMP. (P)

7/14/88 R.W., S.K., K.A.

37.71' N.W. to center hex bolt top 96" CMP. (P)

36.83' N.E. to center USGS Sta. "SHIDLER-1947". (P)

32.72' S.E. to "+" east end headwall. (P)

38.56' S.W. to center hex bolt top 96" CMP. (P)

8/27/79 R.W., J.J., C.S.

B - Found recorded RR spike over high point of stone (8"x9"x14") 16" below road surface. Also found clay tile over stone. Placed RR spike with chiseled "+" over high point of stone. Pk's 6' north and west. Stone is 9.0' north of south edge 18' pavement.

117.33' W.N.W. to duplex s/s power pole.

57.97' S.E. to duplex n/s power pole.

41.37' S.S.E. to center USGS Sta. "SPANGLER-1959". (P)

138.57' W.S.W. to duplex n/s power pole.


7/14/88 R.W., S.K., K.A.

24.22' N. to "+" west end conc. pipe. (P)

33.94' N.E. to "+" east end conc. pipe. (P)

41.37' S.S.E. to center USGS Sta. "SPANGLER-1959". (P)

57.91' S.E. to duplex n/s power pole.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N R- 8 - E

SECTION: 9

9/12/79 R.W., J.J., C.S.

C - Found nail/shiner 1.5' south and 0.80' west of high point of stone (9"x10"x11") 9" below road surface. Removed nail/shiner and placed center punched RR spike on surface over high point of stone. Pk's 6' south and east. Stone is 4.5' east of west edge 18' pavement.

68.95' N.W. to duplex e/s power pole.

7/14/88 R.W., S.K., K.A.

68.81' N.W. to duplex e/s power pole.

19.12' N.E. to 5/8" iron pin at east edge pavement.

20.44' S.E. to 5/8" iron pin at east edge pavement.

5/9/83 R.W., D.B., J.B.

D - Found stone (8"x11"x16") flush with grade. Placed 5/8" iron pin on w/s of stone to aid in locating stone. Set Pk's 8' northeast and southeast. Stone is 4' west of west edge pavement.

26.83' E. to center USGS Sta. "FLORENCE-1950".

26.81' E. to duplex s/s power pole.

30.54' E.S.E. to "+" NE corner catch basin.

16.37' S.W. to Pk west end CMP.


7/14/88 R.W., S.K., K.A.

31.30' N.E. to 5/8" iron pin 1' east of pavement.

26.90' E. to duplex s/s power pole.

26.91' E.S.E. to center USGS Sta. "FLORENCE-1950".(P)

16.37' S.W. to Pk nail west end CMP. (P)



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N

R- 8 - E

SECTION: 10

7/31/79 R.W., J.J., G.M.

A - Found recorded RR spike 0.09' north and 0.12' west of top center of stone (4"x7"x16") 17" below road surface. Also found two small stones and wood stake. Removed small stones and wood stake. Placed center punched RR spike on surface over top center of stone. Pk's 6' north and east. Stone is 5.0' east of west edge 18' pavement.

50.34' N.N.W. to "+" top north end 96" CMP. (P)

45.02' N.E. to center well casing. (P)

47.85' N.E. to shiner sw/s power pole.

37.36' S.E. to shiner nw/s telephone pole.

49.35' S.W. to shiner ne/s power pole.

40.78' S.W. to "+" NE corner catch basin. (P)

7/18/88 R.W., S.K., K.A.

Found nail/shiner on surface. Pk's 6' north and east.


50.36' N.N.W. to "+" north end CMP. (P)

47.97' N.E. to shiner sw/s power pole.

55.33' N.E. to center USGS Sta. "GILES 1950".(P)

49.37' S.W. to shiner ne/s power pole.

40.82' S.W. to "+" NE corner catch basin. (P)



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4-N R-8-E

SECTION: 10

8/29/79 R.W., J.J., C.S.

B - Found recorded Pk nail on North Line, Sec. 10 and midway between NE corner and NW corner, Sec. 10. N $\frac{1}{4}$ Post of Sec.10 falls on bridge deck. Removed Pk and placed center punched boat spike in bridge deck. Pk's 6' north and west. Boat spike is 7.8' north of south edge of bridge deck.

- 33.01' N.W. to SW corner west steel guard rail post.
- 21.62' N.E. to SE corner east steel guard rail post.
- 11.86' S.E. to NE corner east steel guard rail post.
- 28.33' S.W. to NW corner west steel guard rail post.
- 45.87' S.S.W. to duplex nw/s power pole.

7/18/88 R.W., S.K., K.A.

- 33.00' N.W. to SW corner steel guard rail post.
- 21.65' N.E. to SE corner steel guard rail post.
- 11.89' S.E. to NE corner steel guard rail post.
- 28.35' S.W. to NW corner steel guard rail post.
- 48.48' S.W. to duplex nw/s power pole.

7/31/79 R.W., J.J., G.M.


C - Found recorded RR spike over iron pipe, over high point of stone (6"x11"x17") 12" below road surface. Removed iron pipe. Placed center punched RR spike on surface over high point of stone. Pk's 6' north and east. Stone is 1.0' east of west edge 18' pavement.

- 19.56' W.S.W. to "+" top north end 24" RCP. (P)
- 32.51' W. to shiner e/s power pole.
- 70.81' S.S.E. to center USCG Sta. (P) DESTROYED

7/14/88 R.W., S.K., K.A.

Found nail/shiner on surface.

- 38.12' N.E. to Pk nail north end CMP. (P)
- 28.71' E.S.E. to Pk nail south end CMP. (P)
- 19.55' W.S.W. to "+" north end conc. pipe. (P)
- 32.71' W. to shiner e/s power pole.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N R- 8 - E

SECTION: 11


8/28/79 R.W., J.J., C.S.

A - Found recorded iron pin over high point of stone (7"x12"x25") 12" below road surface. Also found wood stake w/s stone and clay tile over stone. Placed center punched RR spike on surface over high point of stone. Pk's 6' north and west. Stone is 2.2' north of south edge 18' pavement.

- 57.63' N.W. to duplex s/s power pole.
- 53.19' E.N.E. to duplex w/s buried cable marker.
- 59.66' E.N.E. to center USGS BM "Y-166". (P)
- 20.34' S.E. to NW corner east bridge rail.
- 22.10' S.S.W. to NE corner west bridge rail.
- 44.99' S.W. to duplex nw/s power pole.

7/18/88 R.W., S.K., K.A.

- 57.63' N.W. to duplex s/s power pole
- 53.25' N.N.E. to duplex w/s buried cable marker.
- 59.65' E.N.E. to center USGS BM "Y116 1947". (P)
- 40.05' S.E. to center USGS Sta. "LYTLE 1947". (P)
- 20.34' S.E. to NW corner bridge rail.
- 22.06' S.S.W. to NE corner bridge rail.
- 52.30' S.W. to duplex nw/s power pole.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N R- 8 - E

SECTION: 11

8/29/79 R.W., J.J., C.S.

B - Found recorded iron pin on n/s stone. Top of iron pin angled over high point of stone (5"x6"x36"). Top of stone is at grade. Placed Pk's 6' northwest and northeast. Stone is 4.5' south of south edge pavement.

72.02' N.W. to spike nw/s power pole.

53.20' N.W. to "+" SE corner catch basin. (P)

130.62' E.N.E. to spike nw/s power pole.

44.46' S.W. to duplex e/s power pole.

7/18/88 R.W., S.K., K.A.

72.11' N.W. to spike e/s power pole.

53.23' N.W. to "+" SE corner catch basin. (P)

44.46' S.W. to duplex e/s power pole.

40.84' S.W. to "+" center conc. headwall. (P)

21.18' N. to Pk nail 1' south of north edge of pavement.

9/13/79 R.W., J.J., C.S.

C - Found stone (9"x10"x12") 14" below road surface. Placed center punched RR spike on surface over high point of stone. Pk's 6' north and east. Stone is 6.6' east of west edge 18' pavement.

115.88' N.N.W. to duplex e/s power pole. GONE

30.19' W.N.W. to "+" top south end conc. block headwall. (P)

72.30' S.S.W. to "+" chiseled west end 8" CMP. (P)

31.75' E. to center USGS Sta. "BRETZ-1947". (P)


7/18/88 R.W., S.K., K.A.

37.83' W. to duplex n/s power pole. (NEW)

30.08' W.N.W. to "+" south end block headwall. (P)

31.75' E. to center USGS Sta. "BRETZ-1947". (P)

72.28' S.S.W. to "+" west end CMP. (P)



COUNTY: HENRY
 TOWNSHIP: RICHFIELD
 T-4 -N R-8 - E
 SECTION: 12

8/29/79 R.W., J.J., C.S.

A - Found recorded RR spike. No stone. RR spike had been established from recorded witness ties. Replaced with center punched RR spike. Pk's 6' south and east. RR spike is 3.9' east of west edge 18' pavement.

- 59.10' N.W. to duplex e/s power pole.
- 53.38' N.N.E. to duplex w/s power pole.
- 24.23' E.S.E. to "+" conc. wingwall. (P)
- 21.66' S.E. to NW corner east bridge rail.
- 13.07' S.W. to NE corner west bridge rail.
- 13.70' W.S.W. to "+" conc. wingwall.
- 52.32' N.E. to center 4" well casing. (P)

7/18/88 R.W., S.K., K.A.

- 68.35' N.W. to duplex e/s power pole. (NEW)
- 53.43' N.N.E. to duplex w/s buried cable marker.
- 52.36' N.E. to center 4" well casing. (P)
- 21.65' S.E. to NW corner bridge rail.
- 13.08' S.W. to NE corner bridge rail.
- 14.61' W.S.W. to "+" center of wing. (P) NEW


8/31/79 R.W., J.J., C.S.

B - Found hinge nail 2.0' west of top center of stone (7"x10"x15") 5" below grade. Removed hinge nail. Placed 5/8"x30" iron pin on n/s stone. Top of iron pin over top center of stone. Pk's 10' northeast and northwest. Stone is 5.5' south of south edge pavement.

- 51.31' N.N.E. to duplex w/s power pole.
- 38.03' S.E. to duplex ne/s 8" elm.
- 35.95' S.W. to duplex e/s telephone pole.

7/19/88 R.W., S.K., K.A.

- 35.22' N.W. to 5/8" iron pin 3' north of pavement.
- 51.38' N.N.E. to duplex w/s power pole.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N R- 8 - E

SECTION: 12

8/30/79 R.W., J.J., C.S.

C - Found iron pin slanted over high point of stone (6"x10"x28") 11" below road surface. Removed iron pin and placed center punched RR spike on surface over high point of stone. Pk's 6' northwest and southwest. Stone is 1' west of ~~west~~^{east} edge 18' pavement.

39.45' W.N.W. to "+" NW end conc. headwall.

39.40' N.N.E. to duplex nw/s telephone pole.

53.31' E.S.E. to duplex n/s power pole.

15.33' S.E. to "+" NW corner conc. headwall.

36.35' S.S.W. to "+" SE corner conc. headwall.

148.50' N. to NW corner, Sec. 7, Milton Twp., Wood Co.

7/19/88 R.W., S.K., K.A.

39.50' W.S.W. to "+" northwest end of headwall.

39.39' N.N.E. to duplex nw/s telephone pole.

53.23' E.S.E. to duplex n/s power pole.

15.29' S.E. to "+" northwest corner headwall.

36.35' S.S.W. to "+" southeast corner headwall.

6/28/77 J.G., B.F., S.B.

D - Found 4" vertical tile over flat stone. Stone is 6" east of west edge 18' pavement. Placed center punched RR spike over stone. Pk's 6' northeast and southeast.

117.52' N.E. to duplex w/s power pole.

89.69' S.E. to duplex w/s power pole.


7/19/88 R.W., S.K., K.A.

29.14' W. to duplex in wood post.

24.80' N.E. to 5/8" iron pin at east edge of pavement.

24.18' S.E. to 5/8" iron pin at east edge of pavement.

89.74' S.S.E. to duplex w/s power pole.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N

R- 8 - E

SECTION: 12

9/17/79 R.W., J.J., C.S.

E - Found recorded iron pin angled over high point of stone(6"x12"x12") 4" below road surface. Removed iron pin and lowered stone to 10" below road surface. Placed center punched RR spike on surface over high point of stone. Pk's 6' north and west. Stone is 4.0' west of east edge 18' pavement.

6.40' E. to center conc. monument 10" below grade. (P)

9.51' S.E. to center conc. monument 10" below grade. (P)

21.73' W.N.W. to Pk ne/s power pole. GONE

116.50' N. to W¼ Post, Sec. 7, Milton Twp., Wood Co.


7/19/88 R.W., S.K., K.A.

17.46' N.W. to 5/8" iron pin at east edge of pavement.

6.37' E. to small hole in center conc. monument. (P)

9.52' S.E. to small hole in center conc. monument. (P)

17.37' S.W. to 5/8" iron pin at west edge of pavement.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N

R- 8 - E

SECTION: 13

6/20/77 R.S., B.F., R.B.


A - Found RR spike 2" deep over brick over high point of stone. Stone is 11" deep. Placed center punched RR spike over high point of stone. Pk's 6' northeast and northwest.

- 40.61' N.W. to duplex ne/s brace pole.
 - 86.39' N.N.E. to duplex w/s power pole.
 - 36.42' W.S.W. to "+" NW end conc. headwall.
 - 35.53' S.W. to "+" in conc. headwall.
 - 46.43' S.E. to "+" in conc. headwall.
 - 49.42' E.S.E. to "+" NE end conc. headwall.
- 7/19/88 R.W., S.K., K.A.
- 40.52' N.W. to duplex ne/s brace pole.
 - 86.40' N.N.E. to duplex w/s power pole.
 - 49.40' E.S.E. to "+" NE end of headwall. (P)
 - 46.41' S.E. to "+" in headwall.
 - 35.54' S.W. to "+" in headwall.
 - 36.49' W.S.W. to "+" NW end of headwall.

9/14/79 R.W., J.J., C.S.

B - Found stone (8"x12"x18") 21" below grade. Found shallow stone over true stone. Removed shallow stone. Placed 5/8"x20" iron pin over top center of stone. Pk's 10' northwest and northeast. Stone is 4.6' south of south edge pavement.

- 86.15' E.N.E. to duplex s/s power pole.
 - 31.65' E.S.E. to "+" NE end of east stone headwall. (P)
 - 31.55' S.S.W. to "+" S end of west stone headwall. (P)
 - 119.13' W. to duplex n/s power pole.
- 7/19/88 R.W., S.K., K.A.
- 86.21' E.N.E. to duplex s/s power pole.
 - 31.67' E.S.E. to "+" NE end stone headwall.
 - 31.49' S.S.E. to "+" S end stone headwall.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N

R- 8 - E

SECTION: 13

9/73 H. Helberg

- C - Found stone. Placed ½"x14" iron pipe over. Pk's 6' south and west.
 40.92' N.W. to Pk ne/s power pole.
 29.34' N.N.E. to Pk w/s brace pole.
 12.70' S.E. to Pk sw/s telephone pole. GONE

7/19/88 R.W., S.K., K.A.

- 40.93' N.W. to Pk nail e/s power pole.
 29.29' N.N.E. to Pk nail w/s brace pole.
 25.25' N.E. to "+" north end conc. pipe. (P)
 26.20' S.E. to "+" NE corner conc. slab. (P)
 44.34' S.S.E. to "+" south end conc. pipe. (P)
 43.30' W.S.W. to "+" west end conc. pipe.

6/28/77 J.G., S.B., B.F.

- D - W¼ Corner, Sec. 13. Found stone over stone. First stone was 7½" deep and second stone is 24½" deep. Also found wood hub along e/s of lower stone. Removed top stone and placed ¾"x30" rebar along e/s of stone with top over stone. Pk's 6' east and south. Rebar is 3" deep. Placed Pk over rebar.

60.69' N.E. to duplex se/s telephone pole.

73.75' S.E. to duplex ne/s telephone pole.

47.49' S.W. to duplex se/s power pole.

5' E. to center line of 18' road.


7/19/88 R.W., S.K., K.A.

Found Pk/rebar and Pk's 6' south and east. Placed RR spike over rebar.

60.66' N.E. to duplex se/s telephone pole.

73.23' S.E. to duplex ne/s telephone pole.

47.45' S.W. to duplex se/s power pole.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4-N

R-8-E

SECTION: 13

9/18/79 R.W., J.J., C.S.

E - Found recorded iron pin over high point of stone (5"x14"x23") 10" below road surface. Removed iron pin. Placed center punched RR spike on surface over high point of stone. Pk's 6' north and west. Stone is 7.7' east of west edge of 15' pavement.

13.61' N.W. to nail in center 4" sq. conc. monument. (P)

11.67' W.S.W. to nail in center 4" sq. conc. monument. (P)

NOTE: Monuments are 3' west of west edge pavement.

139.26' N. to W¹/₄ Post, Sec. 18, Milton Twp., Wood Co.

7/19/88 R.W., S.K., K.A.

13.64' N.W. to center conc. monument. (P)

11.74' W.S.W. to center conc. monument. (P)

A	B
C	

COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4-N R-8-E

SECTION: 14

9/12/79 R.W., J.J., C.S.

A - Found recorded iron pin over small stone 0.70' south of high point of true stone (8"x9"x16") 19" below road surface. Also found second iron pin sw/s true stone. Removed iron pins (2) and small stone. Placed center punched RR spike on surface over high point of stone. Pk's 6' north and west.

42.98' W.N.W. to duplex e/s telephone pole.

43.56' S.S.E. to duplex nw/s power pole.

68.31' S.S.W. to duplex nw/s power pole.

50.64' S.W. to center USGS Sta. "JOESEPH-1947". (P)

7/19/88 R.W., S.K., K.A.

43.00' N.W. to duplex se/s buried cable marker.

34.15' S.E. to "+" east end CMP. (P)

43.56' S.S.E. to spike nw/s power pole.

67.41' S.S.W. to duplex nw/s power pole.

50.64' S.W. to USGS Sta. "JOESEPH-1947". (P)

9/13/79 R.W., J.J., C.S.

B - Found recorded iron pin 0.63' south and 0.20' west of high point of stone (3"x12"x10") 20" below grade. Found two small stones over true stone. Removed iron pin and small stones (2). Set 5/8"x20" iron pin over high point of stone. Pk's 10' northwest and northeast. Stone is 3.0' south of south edge 16' pavement.

29.87' N. to duplex w/s wood anchor post (leans north).

36.86' S.E. to "+" top conc. headwall. (P)


7/19/88 R.W., S.K., K.A.

25.08' N.W. to 5/8" iron pin 1' north of pavement.

25.78' N.E. to 5/8" iron pin 1' north of pavement.

36.87' S.E. to "+" in conc. headwall. (P)

22.25' S.S.E. to "+" in west end conc. pipe. (P)



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N R- 8 - E

SECTION: 14

9/20/79 R.W., J.J., C.S.

C - Found recorded RR spike over high point of stone (3"x10"x13") 26" below road surface. Placed center punched RR spike on surface over high point of stone. Pk's 6' north and west. Stone is 6.5' west of east edge 16' pavement.

32.91' W. to "+" in 8" CMP. (P)

46.60' N.W. to duplex ne/s power pole.

25.08' N.E. to center USCG Sta. "HOSKINSON-1947". (P)

32.63' S.E. to duplex nw/s power pole.


30.50' S.W. to "+" west end 15" CMP.

32.84' W. to "+" east end CMP. (P)

46.64' N.W. to duplex ne/s power pole.

33.39' S.E. to duplex sw/s power pole.

49.94' S.S.E. to "+" center west wall of catch basin. (P)



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N R- 8 - E

SECTION: 15

7/30/79 R.W., J.J., G.M.

A - Found recorded RR spike over high point of stone (6"x8"x19") 8" below road surface. Placed center punched RR spike on surface over high point of stone. Pk's 6' north and west. Stone is 3.0' east of west edge 18' pavement.

34.92' W.N.W. to shiner se/s telephone pole.

33.13' E.N.E. to duplex se/s telephone pole.

46.02' S.S.E. to shiner ne/s telephone pole.

46.88' S.W. to duplex e/s power pole.

7/20/88 R.W., S.K., K.A.

Found nail/shiner on surface.

74.58' W.N.W. to duplex ne/s telephone pole. NEW

37.51' N.E. to center USGS BM "HI16 1947". (P)


33.11' N.E. to duplex (new) nw/s telephone pole.

36.03' S.E. to "+" east end conc. pipe. (P)

66.50' S.S.E. to nail/shiner nw/s telephone pole. NEW

27.42' S.W. to "+" west end conc. pipe. (P)

46.83' S.W. to duplex e/s power pole.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N R- 8 - E

SECTION: 15

9/13/79 R.W., J.J., C.S.

B - Found recorded wood stake at N¼ Post and witness stone 25.00' east of wood stake. Stone is 6"x10"x12" - 4" below grade. Placed 5/8"x30" iron pin on e/s stake. Iron pin marks the true point. Pk's 10' northwest and northeast. Iron pin is 4' south of south edge pavement and stone is 4.9' south of south edge pavement.

Ties to iron pin:

- 30.89' W. to "+" SW conc. bridge wingwall. (P)
- 5.21' N.W. to "+" SE corner conc. bridge deck. (P)
- 31.47' N.N.E. to duplex w/s telephone pole. GONE
- 2.78' S.W. to "+" SE conc. bridge wingwall. (P)
- 25.00' E. to center witness stone.

7/20/88 R.W., S.K., K.A.

Found iron pin. Pk 10' NE; set Pk 10' N.

- 2.78' S.W. to "+" SE wing. (P)
- 30.89' W. to "+" in SW wing. (P)
- 5.24' N.W. to "+" SE corner deck. (P)

Ties to stone:


- 27.28' W. to "+" SE cor. bridge wingwall.
- 36.55' N.W. to duplex w/s telephone pole. GONE
- 25.00' W. to iron pin at N¼ Post, Sec. 15, Richfield Twp.

12/12/01 R.W., S.K.

Set new iron pin at N¼ Post following bridge constuction.

PK nails 10.00' NE & NW

- 34.94 S.S.E. to PK nail east side of power pole.
- 22.65 S.S.W. to sawed "+" southeast corner conc. box. (P)
- 53.06 N.N.W. to sawed "+" northeast corner conc. box. (P)



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N R- 8 - E

SECTION: 15


7/31/79 R.W., J.J., G.M.

C - Found recorded RR spike 1.30' east and 0.05' north of top center of stone (8"x9"x10") 15" below road surface. Placed center punched RR spike on surface over to center of stone. Pk's 6' north and east. Stone is 9.2' east of west edge 18' pavement.

- 25.13' W. to "+" in conc. headwall. (P)
- 31.87' W.N.W. to "+" in conc. headwall. (P)
- 91.85' N.N.W. to shiner se/s power pole.
- 30.91' E.N.E. to shiner sw/s telephone pole.
- 78.20' S.S.W. to shiner ne/s power pole. GONE
- 42.82' W.S.W. to center USGS Sta. "FULLER". (P)
- 22.05' E.S.E. to "+" east end 30" RCP.

7/20/88 R.W., S.K., K.A.

- 25.13' W. to "+" in conc. headwall. (P)
- 32.00' N.W. to "+" in conc. headwall. (P)
- 50.83' N.W. to shiner se/s power pole. NEW
- 30.96' N.E. to shiner sw/s telephone pole.
- 22.07' E.S.E. to "+" east end conc. pipe. (P)
- 42.85' W.S.W. to center USGS Sta. "FULLER 1947". (P)



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N R- 8 - E

SECTION: 16

5/10/83 R.W., D.B., J.B.

A - Found stone (10"x12"x16") 10" below road grade. Placed center punched RR spike on surface over stone. Pk's 6' south and west.

34.78' W.N.W. to SW corner north bridge rail.

16.13' N.W. to SE corner north bridge rail.

75.10' N.E. to duplex s/s power pole.

72.63' E.N.E. to duplex w/s power pole.

15.94' S.W. to NE corner south bridge rail.

43.28' W.S.W. to center USGS witness tablet "RICHARD 2".

7/20/88 R.W., S.K., K.A.

34.75' W.N.W. to SW corner bridge rail.


16.14' N.W. to SE corner bridge rail.

75.12' N.N.E. to duplex s/s power pole.

72.64' E.N.E. to duplex w/s power pole.

15.94' S.W. to NE corner bridge rail.

43.28' W.S.W. to center USGS Sta. "RICHARD 2".



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N R- 8 - E

SECTION: 16

5/10/83 R.W., D.B., J.B.

B - Found stone (9"x9"x8") 11" below road surface. Found wood stake on w/s stone. Placed center punched RR spike on surface over top center of stone. Pk's 6' north and west. Stone is 8.5' north of south edge pavement.

41.62' W.N.W. to Pk west end CMP. (P)

24.13' N.W. to Pk east end CMP. (P)

49.31' N.N.E. to "+" in conc. slab.

40.15' S.W. to duplex se/s tree.

7/20/88 R.W., S.K., K.A.

41.63' W.N.W. to Pk nail west end CMP. (P)

24.13' N.W. to Pk nail east end CMP. (P)

49.31' N.N.E. to ""+" in conc. slab.

14.27' N.E. to 5/8" iron pin at edge of pavement.

11.89' S.E. to 5/8" iron pin at edge of pavement.

9/26/79 R.W., J.J., C.S.

C - Found RR spike over iron pipe, over top center of stone (10"x13"x7"). Found 6" clay tile with 1x2 wood stake under stone. Clay tile is 22" below road surface. Chiseled "+" in stone. "+" is directly over 1x2 stake. Placed center punched RR spike on surface over "+" in stone. Pk's 6' south and west. Stone is 5.5' east of west edge pavement.

32.89' W. to "+" in 4" alum. pipe. (P)

70.83' N.E. to duplex nw/s 24" maple.

32.56' E.N.E. to duplex sw/s 30" maple.

78.48' E. to center USCG Sta. "RICHARD-1947". GONE

7/20/88 R.W., S.K., K.A.


Found RR spike and Pk's 6' south and east.

32.67' W. to "+" in 4" alum. pipe. (P)

71.33' N.N.E. to Pk nail w/s 24" maple. NEW

19.37' N.E. to 5/8" iron pin 1' east of pavement.

21.45' S.E. to 5/8" iron pin 1' east of pavement.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N R- 8 - E

SECTION: 17

6/9/75 J.G., B.B., T.F.


A - Found 5" bolt over stone. Stone was 12" deep. Replaced bolt with RR spike. Pk's 6' northeast and southeast.

- 56.56' N.E. to 30d spike w/s power pole.
- 42.73' N.E. to 30d spike nw/s telephone pole.
- 43.79' N.W. to 30d spike s/s power pole.
- 33.93' S.E. to "+" in headwall.
- 7/21/88 R.W., S.K., K.A.
- 43.78' N.W. to spike s/s power pole.
- 22.34' N.W. to "+" NE corner bridge deck.
- 59.54' N.E. to duplex w/s power pole.
- 42.79' N.E. to spike w/s telephone pole.
- 34.08' S.E. to "+" center conc. headwall.
- 17.91' W.S.W. to "+" SE corner bridge deck.

9/7/79 R.W., J.J., C.S.

B - Found recorded RR spike over top center of stone (10"x10"x15") 12" below road surface. Placed center punched RR spike on surface over top center of stone. Pk's 6' south and east. Stone is 3.9' south of north edge 12' pavement.

- 50.46' W.N.W. to duplex s/s 20" maple.
- 73.00' N.W. to SE corner house foundation.
- 10.54' N.E. to SW corner north conc. bridge rail.
- 13.04' S.E. to NW corner south conc. bridge rail.
- 7/21/88 R.W., S.K., K.A.
- Set Pk nail 6' west of RR spike.
- 50.37' W.N.W. to Pk nail (new) s/s 24" maple.
- 73.16' N.W. to duplex SE corner house in wood siding.
- 10.52' N.E. to SE corner conc. banister.
- 13.04' S.E. to NW corner conc. banister.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N R- 8 - E

SECTION: 17

10/10/79 R.W., J.J., C.S.

C - Found stone (10"x16"x22"), top of stone is at grade. Placed 1/2"x12" iron pin horizontally on e/s stone to aid in locating stone. Pk's 15' northeast and southeast. Stone is 10.1' west of west edge 10' pavement.

No ties available.

7/21/88 R.W., S.K., K.A.

15.06' N.E. to Pk nail. (P)

28.07' N.E. to 5/8" iron pin 3' east of pavement. (P)

15.08' S.E. to Pk nail. (P)

29.05' S.E. to 5/8" iron pin 3' east of pavement. (P)

5/9/83 R.W., D.B., J.B.

D - Found stone (8"x9"x12") 10" below road surface. Placed center punched RR spike on surface over top center of stone. Pk's 6' north and west. Stone is 7.2' south of north edge pavement.

37.82' N. to duplex w/s wood anchor post.

17.41' S.E. to 5/8" iron pin at south edge pavement.


21.05' S.W. to 5/8" iron pin at south edge pavement.

7/21/88 R.W., S.K., K.A.

37.81' N. to duplex w/s wood anchor post.

17.41' S.E. to 5/8" iron pin at south edge pavement.

21.11' S.W. to 5/8" iron pin at south edge pavement.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N R- 8 - E

SECTION: 18

5/3/79

A - Found recorded iron pin on sw/s of stone with top of pin over high point of stone (4"x7"x4"). Stone is 6" below ground level. Pk's 10' southeast and northeast. Stone is 6.2' west of west edge pavement.

- 58.55' N.N.W. to "+" south end conc. pipe.
- 56.75' N.E. to spike sw/s power pole.
- 37.86' S.E. to "+" NE end conc. headwall. (P)

7/21/88 R.W., S.K., K.A.

- 58.42' N.N.W. to "+" south end conc. pipe. (P)
- 56.67' N.E. to spike sw/s power pole.
- 38.00' S.E. to "+" NE end conc. headwall. (P)


9/10/79 R.W., C.S.

B - Searched for stone, did not locate. Reestablished N¹/₄ Post, Sec. 18, by single proportionate measurement along the North Line of Sec. 18 between the NE corner and NW corner of Sec. 18. Placed center punched RR spike on surface. Pk's 6' north and east. RR spike is 2.2' north of south edge 14' pavement.

- 19.65' N. to "+" NW conc. wingwall.
- 23.86' N.E. to "+" NE conc. wingwall.
- 16.03' E.S.E. to "+" SE conc. wingwall. (P)
- 7.30' S. to "+" SW conc. wingwall. (P)

7/21/88 R.W., S.K., K.A.

- Found RR spike and Pk's 6' northwest and northeast.
- 19.34' N.W. to 5/8" iron pin at north edge pavement.
- 29.11' N.N.E. to "+" north end conc. pipe. (P)
- 32.95' E.S.E. to 5/8" iron pin at south edge pavement.
- 19.99' S.S.E. to "+" south end conc. pipe. (P)



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N R- 8 - E

SECTION: 18

10/11/79 R.W., J.J., C.S.

C - Searched for stone, did not locate. Reestablished W $\frac{1}{4}$ Post on East Line of Sec. 13, Monroe Twp. and midway between the NW corner and SW corner of Sec. 18, Richfield Twp. Placed 5/8"x20" iron pin at W $\frac{1}{4}$ Post. Pk's 6' northeast and southeast. Iron pin is 0.5' west of west edge pavement.

64.00' N. to iron pin at E $\frac{1}{4}$ Post, Sec. 13; Monroe Twp.

64.89' N.N.E. to center USGS Sta. "COUCH-1948". (P)

26.56' E.N.E. to 60d spike n/s power pole.

104.35' S.S.W. to duplex w/s mail box post.


7/21/88 R.W., S.K., K.A.

Found iron pin. Set Pk's 6' northeast and southeast.

64.87' N.N.E. to center USGS Sta. "COUCH-1948". (P)

26.28' E.N.E. to duplex s/s power pole.

27.13' S.E. to 5/8" iron pin at east edge pavement.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 - N R- 8 - E

SECTION: 19

10/4/79 R.W., J.J., C.S.

A - Found clay tile over stone (8"x11"x14") 10" below road surface. Placed center punched RR spike on East Line of Sec. 24, Monroe Twp. at the point of intersection with the North Line of Sec. 19, Richfield Twp. Top center of stone is 0.51' east of RR spike. Pk's 6' south and east. Stone is 3.4' east of west edge 16' pavement.

- 81.72' N.N.E. to Pk w/s power pole.
- 58.18' E.N.E. to "+" NW corner catch basin. (P)
- 23.66' W.S.W. to "+" north end conc. headwall. (P)
- 60.84' N. to NE corner, Sec. 24; Monroe Twp.


7/21/88 R.W., S.K., K.A.

- 35.00' N.W. to "+" south end conc. pipe. (P)
- 81.71' N.N.E. to Pk nail w/s power pole.
- 60.26' E.N.E. to center USGS BM "F117 1947". (P)
- 58.18' E.N.E. to "+" NW corner catch basin. (P)
- 23.65' S.W. to "+" north end conc. headwall. (P)

10/10/79 R.W., J.J., G.M.

B - Found stone (6"x18"x18") 11" below road surface. Placed center punched RR spike on surface over top center of stone. Pk's 6' north and west. Stone is 6.5' north of south edge 18' pavement.

- 49.87' W.N.W. to "+" SE corner catch basin. (P)
 - 35.01' E.N.E. to "+" SE corner catch basin. (P)
 - 30.46' S.S.E. to "+" in conc. slab. (P)
- 7/21/88 R.W., S.K., K.A.
- 49.85' N.W. to "+" SE corner catch basin. (P)
 - 35.01' N.E. to "+" SE corner catch basin. (P)
 - 30.44' S.S.E. to "+" in conc. slab. (P)



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N R- 8 - E

SECTION: 19

10/16/79 R.W., C.S.

C - Searched for stone, did not locate. Reestablished W¹/₄ Post by single proportionate measurement along the West Line, Sec. 19. Placed center punched RR spike on the East Line of Sec. 24; Monroe Twp. Pk's 6' northeast and southeast. RR spike is 2.0' east of west edge 18' pavement.

32.64' N.N.W. to 5/8"x30" iron pin at west edge pavement.

60.88' N.N.E. to duplex s/s power pole.

16.35' S.S.W. to 5/8"x30" iron pin at west edge pavement.


58.45' N. to E¹/₄ Post, Sec. 24; Monroe Twp.

7/21/88 R.W., S.K., K.A.

32.63' N.N.W. to 5/8" iron pin at west edge pavement.

60.90' N.N.E. to duplex s/s power pole.

16.36' S.S.W. to 5/8" iron pin at west edge pavement.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4-N R-8-E

SECTION: 20

10/9/79 R.W., J.J., C.S.

A - Found fractured stone (9"x12"x12") 17" below road surface. Found clay brick and three small stones over stone. Placed center punched RR spike on surface over top center of stone. Pk's 6' north and west. Stone is 9' south of north edge 18' east-west pavement.

- 21.05' N.W. to "+" NE bridge wingwall. (P)
- 46.20' N.E. to duplex nw/s telephone pole.
- 41.09' S.E. to nail in conc. headwall.
- 19.00' S.W. to duplex e/s middle guard rail post.

7/21/88 R.W., S.K., K.A.

- 21.06' N.W. to "+" NE bridge wing.
- 46.04' N.E. to duplex se/s telephone pole. NEW
- 46.80' N.E. to center USGS Sta. "SCHOOL 1950". (P) (left RR spike over monument for magnetic locators.

41.09' S.E. to Pk nail in center conc. headwall.

20.91' S.W. to "+" SE corner bridge deck. (P)


10/4/79 R.W., J.J., C.S.

B - Found recorded iron pin over high point of stone (5"x7"x21") 15" below road surface. Removed iron pin. Placed center punched RR spike on surface over high point of stone. Pk's 6' north and west. Stone is 9.3' north of south edge 18' pavement.

- 29.05' N. to duplex s/s wood anchor post.
- 74.56' N. to center USGS Sta. "DICKMANDER-1950". (P)
- 34.90' N.E. to "+" SW cor. catch basin. (P)
- 34.91' S.E. to "+" S. end 12" RCP. (P)

7/21/88 R.W., S.K., K.A.

- 29.06' N. to duplex w/s wood post. (loose)
- 74.56' N. to USGS Sta. "DICKMANDER-1950". (P)
- 29.36' N. to duplex e/s power pole.
- 34.94' N.E. to "+" SW corner catch basin. (P)
- 32.53' S.E. to "+" (new) south end conc. pipe. (P)



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N R- 8 - E

SECTION: 20


10/4/79 R.W., J.J., C.S.

C - Found stone (9"x12"x13") 10" below grade. Found wood stake and clay tile over stone. Placed 5/8"x30" iron pin angled over top center of stone. Pk's 15' northeast and southeast. Stone is 6' west of west edge 18' pavement.

- 40.58' N.E. to duplex nw/s power pole.
- 33.70' E. to duplex nw/s wood anchor post.
- 35.48' E. to USGS Sta. "SIEGFRED-1950". (P)
- 25.09' S.W. to "+" chiseled in end of 8" CMP. (P)
- 37.77' W. to "+" chiseled in top of large rock.

7/21/88 R.W., S.K., K.A.

- 40.58' N.E. to duplex nw/s telephone pole.
- 35.43' E. to USGS Sta. "SIEGFRED-1950". (P)
- 33.62' E. to duplex n/s wood post. (loose)
- 24.84' S.W. to Pk nail west end CMP. (P)



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N

R- 8 - E

SECTION:

21

9/25/79 R.W., J.J., C.S.

A - Found iron bolt 0.15' south and 0.07' west of high point of stone (10"x14"x26") 15" below road surface. Removed iron bolt. Placed center punched RR spike on surface over high point of stone. Pk's 6' north and west. Stone is 6.8' north of south edge 18' pavement.

47.26' N.W. to duplex se/s power pole.

41.89' N.N.W. to "+" N. end 90" RCP. (P)

40.39' N.E. to duplex sw/s telephone pole.

38.99' S.E. to "+" NE corner catch basin. (P)

43.40' S.W. to "+" S. end 90" RCP. (P)

40.87' N.E. to "+" SE corner catch basin. (P)

7/21/88 R.W., S.K., K.A.

47.25' N.W. to duplex se/s power pole.

41.88' N.W. to "+" north end conc. pipe. (P)

44.65' N.E. to center Sta. "FICKLE 1947". (P)

40.85' N.E. to "+" SE corner catch basin. (P)

9/28/79 R.W., J.J., C.S.

B - Searched for stone, did not locate. Reestablished N¼ Post by single proportionate measurement along the South Line of Sec. 16, between the SW corner and the SW corner, SE ¼, SE¼; Sec. 16. Placed center punched RR spike on surface. Pk's 6' north and west. RR spike is 4.5' north of south edge 18' pavement.

27.11' N.W. to "+" SW corner catch basin. (P)

35.39' S.E. to duplex ne/s wood anchor post.

28.47' S.W. to duplex nw/s wood anchor post. GONE


33.26' N.N.W. to center USCG Sta. "ALVAH 1947". (P)

7/21/88 R.W., S.K., K.A.

27.10' N.W. to "+" SW corner catch basin. (P)

33.28' N. to center Sta. "ALVAH 1947". (P)

13.94' S. to Pk nail south end CMP. (P)



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N R- 8 - E

SECTION: 21

9/28/79 R.W., J.J., C.S.

C - Found Pk 1.10' south and 0.50' west of top center of stone (8"x11"x13") 16" below road surface. Removed Pk. Placed center punched RR spike on surface over high point of stone. Pk's 6' north and west. Stone is 2.5' north of south edge 18' pavement.

- 51.12' N. to duplex w/s 30" maple.
- 35.02' N.N.E. to duplex w/s power pole.
- 31.83' S. to duplex w/s power pole.

7/21/88 R.W., S.K., K.A.

- 21.69' N.W. to 5/8" iron pin at north edge pavement.
- 51.13' N. to duplex w/s 33" maple.
- 35.06' N.N.E. to duplex w/s power pole.
- 30.01' N. to property pin.
- 31.76' S. to duplex w/s power pole.


9/28/79 R.W., J.J., C.S.

D - Found iron pin over high point of stone (9"x14"x12") 12" below road surface. Removed iron pin. Placed center punched RR spike on surface over high point of stone. Pk's 6' south and east. Stone is 5.4' east of west edge 18' pavement.

- 28.12' E. to duplex n/s power pole. (P)
- 26.66' S.E. to NW corner catch basin. (P)
- 28.27' E.S.E. to center USCG Sta. "JOHN-1950". (P)
- 28.84' S.W. to "+" in 8" CMP, 4.5' from end. (P)

7/21/88 R.W., S.K., K.A.

- 28.12' E. to duplex n/s power pole.
- 28.29' E. to center Sta. "JOHN-1950". (P)
- 26.66' S.E. to "+" NW corner catch basin. (P)
- 28.12' E. to duplex n/s power pole.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4 -N R-8 -E

SECTION: 22

7/30/79 R.W., J.J., G.M.

A - Found recorded RR spike 0.63' east of high point of stone (4"x6"x24") 26" below road surface. Found wood stake on e/s stone. Placed center punched RR spike on surface over high point of stone. Pk's 6' north and west. Stone is 8.2' east of west edge 18' pavement.

- 47.91' N.W. to SE corner conc. walk.
- 38.99' S.E. to shiner nw/s telephone pole.
- 74.03' S.S.E. to shiner nw/s 32" maple.
- 45.13' S.S.W. to shiner ne/s power pole.

7/25/88 R.W., S.K.

- 83.06' W.N.W. to nail/shiner se/s telephone pole.
- 41.78' S.E. to nail/shiner ne/s power pole. NEW
- 74.01' S.S.E. to duplex n/s maple.
- 45.38' S.W. to nail/shiner ne/s power pole.


9/24/79 R.W., J.J., C.S.

B - Found iron pin 0.10' south of top center of stone (4"x5"x22") 16" below road surface. Removed iron pin. Placed center punched RR spike over top center of stone. Pk's 6' north and west. Stone is 1.8' north of south edge 18' pavement.

- 23.28' N. to "+" SW corner catch basin. (P)
- 27.22' N.N.E. to duplex nw/s telephone pole.
- 101.65' E.N.E. to duplex s/s 24" maple.

7/25/88 R.W., S.K.

- 20.80' N.W. to 5/8" iron pin at north edge pavement.
- 23.30' N. to "+" SW corner catch basin. (P)
- 27.27' N.N.E. to duplex nw/s telephone pole.
- 22.66' N.E. to 5/8" iron pin at north edge pavement.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4-N

R-8-E

SECTION: 22


9/25/79 R.W., J.J., C.S.
 C - Searched for stone, did not locate. Reestablished N¹/₄ Post by single proportionate measurement along the North Line, Sec. 22 between the NW corner, NE¹/₄, NW¹/₄ and the NE corner of Sec. 22. Placed center punched RR spike on surface. Pk's 6' south and west. RR spike is 3.6' south of north edge 18' pavement.

- 7.25' N. to Pk e/s guard rail post.
- 15.95' N.E. to "+" NE bridge wingwall.
- 20.63' S.E. to "+" SE bridge wingwall. (P)
- 17.39' S. to "+" SW bridge wingwall. (P)

- 7/25/88 R.W., S.K.
- 7.33' N. to Pk nail e/s guard rail post.
 - 9.63' N. to "+" in conc. wing.
 - 15.94' N.E. to "+" in conc. wing.
 - 20.66' S.E. to "+" in conc. wing.
 - 17.43' S. to "+" in conc. wing.
 - 54.60' S.W. to duplex n/s telephone pole.

9/24/79 R.W., J.J., C.S.
 D - Searched for stone, did not locate. Reestablished NW corner, NE¹/₄, NE¹/₄ of Sec. 22 by single proportionate measurement along the North Line, Sec. 22 between the NE corner and the NW corner, NE¹/₄, NW¹/₄ of Sec. 22. Placed center punched RR spike on surface. Pk's 6' south and west. RR spike is 6.3' south of north edge 18' pavement.

- 117.94' W.N.W. to duplex s/s telephone pole. GONE
 - 48.37' N.E. to duplex w/s telephone pole.
 - 30.56' S. to duplex w/s wood post.
 - 98.38' W.S.W. to duplex n/s power pole.
- 7/25/88 R.W., S.K.
- 48.40' N.E. to duplex s/s telephone pole.
 - 98.38' W.S.W. to duplex n/s power pole.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N

R- 8 - E

SECTION: 22


7/26/79 R.W., J.J., G.M.

E - Found recorded RR spike over stones, 0.22' north and 0.04' east of high point of true stone (3"x5"x19") 17" below road surface. Removed top stones and placed center punched RR spike on surface over high point of true stone. Pk's 6' north and east. Stone is 2.9' east of west edge 18' pavement.

- 54.57' W. to "+" in conc. corn crib foundation. GONE
- 33.19' N.N.W. to "+" S. end 60" metal pipe.
- 47.85' N.N.W. to "+" N. end 60" metal pipe.
- 29.45' E. to shiner w/s corner fence post.
- 45.54' S.S.W. to shiner ne/s power pole.
- 29.17' S.W. to "+" in end of 21" CMP.
- 23.35' E.S.E. to "+" S. end conc. headwall.

7/25/88 R.W., S.K.

- 19.61' N.W. to "+" NW end conc. pipe. (P)
- 33.19' N.W. to "+" south end metal pipe. (P)
- 47.87' N.N.W. to "+" north end metal pipe.
- 23.44' E.S.E. to "+" south end conc. headwall. (P)
- 45.53' S.W. to nail/shiner ne/s power pole.
- 29.18' S.W. to "+" east end CMP. (P)



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N R- 8 - E

SECTION: 23

9/21/79 R.W., J.J., C.S.

A - Found clay tile over stone(6"x8"x17") 16" below road surface. Placed center punched RR spike on surface over top center of stone. Pk's 6' south and west. Stone is on center line of east-west pavement.

- 23.35' N.W. to "+" in conc. headwall.
- 35.39' N.E. to "+" SE corner catch basin. (P)
- 39.32' S.E. to duplex w/s power pole.
- 24.00' S.W. to "+" in conc. headwall.

7/28/88 R.W., S.K.

- 23.36' N.W. to "+" in center conc. headwall.
- 35.40' N.E. to "+" SE corner catch basin. (P)
- 39.33' S.E. to duplex sw/s power pole.
- 24.01' S.W. to "+" in center conc. headwall.
- 43.80' N.E. to iron pin in 10" dia. conc. monument.


12/9/82 R.W., D.B., J.B.

B - Found stone (2"x12"x8") 13" below road surface. Placed center punched RR spike on surface over top center of stone. Pk's 6' south and west. Stone is 5.0' south of north edge 18' pavement.

- 27.56' N. to bolt at base of conc. corner post.
- 24.99' N.N.E. to duplex se/s telephone pole.

7/25/88 R.W., S.K.

- 27.54' N. to bolt at base of conc. corner post.
- 24.98' N.N.E. to duplex se/s telephone pole.
- 18.91' S.E. to 5/8" iron pin at south edge pavement.
- 17.03' S.W. to 5/8" iron pin at south edge pavement.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N R- 8 - E

SECTION: 23

12/10/82 R.W., D.B., J.B.

C - No stone. Reestablished N $\frac{1}{4}$ Post midway between and on line with the NW corner, NE $\frac{1}{4}$, NW $\frac{1}{4}$, and the NE corner, NW $\frac{1}{4}$, NE $\frac{1}{4}$ of Sec. 23. Placed center punched RR spike on surface. Pk's 6' south and west. RR spike is 5.7' south of north edge 18' pavement. Removed an iron pin 6.5' north established by a previous survey.

80.17' W.N.W. to duplex s/s telephone pole.

80.59' E.N.E. to duplex s/s telephone pole.

27.59' S. to iron pipe in base of conc. anchor post.

7/25/88 R.W., S.K.

80.15' W.N.W. to duplex s/s telephone pole.

80.61' E.N.E. to duplex s/s telephone pole.

27.58' S. to iron pipe in base of conc. anchor post.

12/9/82 R.W., D.B., J.B.

D - Found Pk over top center of stone (4"x15"x8") 9" below road surface. Placed center punched RR spike on surface over top center of stone. Stone is 3.7' south of north edge 18' pavement.

39.53' W.N.W. to spike se/s telephone pole.

83.20' E.S.E. to spike nw/s power pole.

101.55' W.S.W. to spike ne/s power pole.


7/25/88 R.W., S.K.

39.56' W.N.W. to duplex se/s telephone pole.

83.18' E.S.E. to duplex nw/s power pole.

19.79' S.E. to 5/8" iron pin at south edge pavement.

18.43' S.W. to 5/8" iron pin at south edge pavement.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T- 4 -N

R- 8 - E

SECTION: 23

9/21/79 R.W., J.J., C.S.

E - Found iron pin over high point of stone (3"x6"x23") 11" below edge of pavement. Pk's 6' northeast and southeast. Iron pin is on the west edge of pavement.

23.51' W.N.W. to chiseled "+" east end 8" CMP. (P)

27.49' S.W. to 1"x33" iron pipe on west ditch bank. (P)


7/25/88 R.W., S.K.

23.44' W.N.W. to "+" east end CMP. (P)

24.50' N.E. to 5/8" iron pin at east edge pavement.

23.05' S.E. to 5/8" iron pin at east edge pavement.

27.54' S.W. to 1" iron pipe.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4-N R-8-E


SECTION: 24

11/73 H. Helberg

- A - Found stone 15" deep. Placed RR spike over stone. Pk's 6' north, east, and southwest.
 65.29' N.W. to face well casing.
 33.52' N.W. to "+" in west wall catch basin.
 34.45' S.W. to Pk e/s power pole.
 75.92' N.N.E. to Pk e/s telephone pole.
 7/26/88 R.W., S.K.
 Found Pk's 6' north and east.
 39.65' N.W. to duplex ne/s telephone pole.
 32.51' N.W. to "+" SW corner catch basin. (P)
 77.99' E.N.E. to duplex n/s brace pole.
 38.54' S.E. to duplex e/s telephone pole.
 30.52' S.E. to "+" east end conc. pipe. (P)
 26.08' S.W. to "+" west end conc. pipe. (P)
 35.60' S.W. to duplex se/s power pole.

9/19/79 R.W., J.J., C.S.

- B - A previous search for stone had been made as evidenced by patches in road pavement. Reestablished N¼ Post by single proportionate measurement along the North Line of Sec. 24 between the NE corner and the NW corner of Sec. 24. Placed center punched RR spike on surface. Pk's 6' north and west. RR spike is 2.0' north of south edge 14' pavement.
 20.89' N. to "+" north end conc. pipe. (P)
 102.01' N.E. to duplex s/s power pole.
 18.75' S. to "+" NE corner catch basin. (P)
 7/26/88 R.W. S.K.
 18.05' N.W. to 5/8" iron pin at north edge pavement.
 22.63' N.N.E. to "+" north end clay pipe. (P)
 102.19' E.N.E. to duplex se/s power pole.
 18.73' S.S.E. to "+" NE corner catch basin. (P)
 9.51' S.W. to 5/8" iron pin at south edge pavement.



COUNTY: HENRY
 TOWNSHIP: RICHFIELD
 T-4-N R-8-E
 SECTION: 24

5/24/77 J.G., B.F., R.B.
 C - NE corner, Sec. 24, Richfield Twp. Found 1/2" I. P. angled over top center of stone. I.P. was 6" deep and stone was 9" deep. Stone was badly fractured. Placed Pk's 4' northwest and northeast.


- 63.23' S.W. to duplex e/s brace pole.
- 74.00' N.W. to SE corner conc. catch basin.
- 56.91' N.W. to duplex ne/s power pole.

7/26/88 R.W., S.K.
 74.29' W.N.W. to "+" SE corner catch basin. (P)
 56.99' N.W. to duplex ne/s power pole.
 23.01' S.E. to "+" east end conc. pipe.
 61.34' S.S.W. to duplex nw/s brace pole.
 71.24' W.S.W. to "+" NE corner catch basin. (P)

10/23/79 R.W., J.J., C.S.
 D - Searched for stone, did not locate. Reestablished W 1/4 Post at midpoint of West Line, Sec. 24. Placed center punched RR spike on surface. Pk's 6' north and west. RR spike is 2.1' east of west edge 18' pavement.

- 76.37' N.N.W. to duplex e/s power pole.
- 25.47' E.S.E. to duplex n/s telephone pole. GONE

7/26/88 R.W., S.K.
 Found Pk nails 6' north and east.
 76.40' N.N.W. to duplex ne/s power pole.
 106.30' N.N.E. to duplex se/s telephone pole.
 31.62' N.E. to 5/8" iron pin 1' east of pavement.
 26.17' S.E. to 5/8" iron pin 1' east of pavement.
 69.54' S.S.E. to duplex ne/s telephone pole.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4-N R-8-E


SECTION: 24

R.S., J.G., B.B., T.F.

- E - Set RR spike over stone. Stone is 1' deep. Pk's 10' northwest and southwest.
 17.60' N.W. to 5/8" iron pin at west edge 16' pavement.
 6.77' E. to 5/8" iron pin at east edge 16' pavement.
 16.88' S.W. to 5/8" iron pin at west edge 16' pavement.
 118.97' N. to W¼ Post, Sec. 19, Milton Twp., Wood Co.

7/26/88 R.W., S.K.

- 17.58' N.W. to 5/8" iron pin at west edge 16' pavement.
 14.00' E.N.E. to "+" east end clay pipe. (P)
 6.78' E. to 5/8" iron pin at east edge 16' pavement.
 16.90' S.W. to 5/8" iron pin at west edge 16' pavement.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4-N R-8-E

SECTION: 25

8/7/79 R.W., J.J., C.S.

A - Found recorded boat spike and square spike (8" long). No stone found. Corner had been established from witness ties for S.H. #591 in ODOT office. Replaced square spike on surface. Pk's 6' north and west.

74.73' N.N.W. to shiner s/s power pole.

94.54' N.E. to SW corner house foundation.

67.88' S.S.E. to duplex w/s telephone pole.

59.08' S.S.W. to shiner ne/s power pole.

7/26/88 R.W., S.K. Found baby RR spike on surface. No Pk's.

63.95' N.N.W. to duplex sw/s power pole.

54.06' N.N.W. to "+" in center conc. headwall. (P)

55.01' N.N.E. to shiner s/s telephone pole.

33.03' S.S.E. to "+" in conc. structure. (P)

67.92' S.S.E. to duplex sw/s telephone pole.

58.87' S.S.W. to duplex nw/s power pole.

10/25/79 R.W., J.J., C.S.

B - Found recorded RR spike 0.37' south of high point of true stone (5"x7"x17") 22" below road surface. Also found smaller stone over true stone. Removed RR spike and small stone. Placed center punched RR spike on surface over high point of stone. Pk's 6' northwest and northeast. Stone is 0.8' south of south edge 18' pavement.

51.42' N.W. to "+" NE corner catch basin. (P)

51.58' N. to near face Dekalb sign post.

92.37' E.S.E. to "+" in NW bridge wingwall.

42.39' S.W. to "+" south end RCP. (P)


7/26/88 R.W., S.K. Found baby RR spike. No Pk's

49.17' N.W. to "+" SE corner catch basin. (P)

92.30' E.S.E. to "+" northwest wing of bridge. (P)

97.36' S. to NW corner of conc. foundation.

41.21' S.W. to "+" south end conc. pipe. (plumbed 6' above "+")



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4-N R-8-E

SECTION: 25

8/7/79 R.W., J.J., G.M.

C - Found recorded RR spike and boat spike 0.17' north of stone (8"x10"x20") 21" below road surface. Also found wood stake s/s stone. Removed RR spike, boat spike and wood stake. Placed center punched RR spike on surface over stone. Pk's 6' north and east. Stone is 0.8' south of south edge pavement, SR 281.

78.35' N.W. to shiner e/s telephone pole.

70.67' N.N.E. to "+" east end stone headwall.

26.65' E.S.E. to drill hole, north end conc. headwall. (P)

61.18' S.S.W. to shiner in power pole.

52.80' N. to NW corner, Sec. 30, Milton Twp., Wood Co.

7/26/88 R.W., S.K. Found baby RR spike. No Pk's.

78.35' N.W. to shiner e/s telephone pole.

46.74' N.W. to "+" NE corner catch basin. (P)

70.70' N.N.E. to "+" east end stone headwall. (P)

83.30' N.N.E. to shiner sw/s telephone pole.

31.18' S.E. to "+" NE corner catch basin. (P)

90.90' S.S.E. to shiner n/s power pole.

10/22/79 R.W., J.J., C.S.

D - Found stone (4"x8"x18") 19" below road surface. Placed center punched RR spike on surface over top center of stone. Pk's 6' north and east. Stone is 5.4' east of west edge 18' pavement and 6.0' south of north edge 14' pavement.

17.29' N.W. to SE corner north bridge rail.

36.65' N.W. to duplex s/s power pole.

66.60' N.N.E. to duplex w/s telephone pole.

18.28' S.W. to NE corner south bridge rail.

86.40' W.S.W. to duplex n/s 20" catalpa.


7/27/88 R.W., S.K., K.A.

44.84' N.W. to duplex sw/s power pole.

30.72' N.W. to "+" north end RCP. (P)

67.55' N.N.E. to duplex w/s telephone pole.

32.56' S.W. to "+" south end RCP. (P)



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4-N R-8-E

SECTION: 25

10/18/79 R.W., C.S.

E - Found stone (3"x4"x16"). Top of stone is at grade on east ditch bank. Placed 5/8"x30" iron pin on e/s stone. Top of iron pin is over high point of stone. Pk's 12' northeast and southeast. Stone is 6.7' west of west edge 15' pavement.

30.97' N.W. to 5/8"x30" iron pin on west ditch bank.

32.22' N.E. to 5/8"x30" iron pin at east edge 15' pavement. (P)

29.23' S.W. to 5/8"x30" iron pin on west ditch bank.

51.43' N. to W $\frac{1}{4}$ Post, Sec. 30, Milton Twp., Wood Co.

7/27/88 R.W., S.K., K.A.


Found iron pin and Pk's. Stone had moved 0.12' west down ditch bank. Iron pin and Pk's mark true position of W $\frac{1}{4}$ Post.

30.86' N.W. to 5/8" iron pin on west ditch bank. (mark to mark)

55.31' N.N.W. to "+" west end CMP. (P)

63.77' N.E. to "+" south end conc. drainage structure. (P)

25.51' S.W. to 5/8" iron pin on west ditch bank. (mark to mark)



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4-N R-8-E

SECTION: 26

8/8/79 R.W., J.J., G.M.

A - Found iron pin in clay tile over high point of stone (8"x8"x10") 12" below road surface. Also found flat stone (8"x10"x4") under true stone. Removed iron pin. Placed center punched RR spike on surface over high point of true stone. Pk's 6' north and west. Stone is 4.2' north of south edge 18' pavement.

- 48.37' N.W. to 60d spike e/s brace pole.
- 34.51' S.E. to "+" in conc. headwall.
- 29.43' S.W. to "+" in conc. headwall.
- 52.35' N.W. to center USGS BM "A-117 1947".


7/27/88 R.W., S.K., K.A. Found baby RR spike. No Pk's

- 52.35' N.W. to center USGS BM "A-117 1947".
- 48.37' N.W. to 60d spike e/s brace pole.
- 34.54' S.E. to "+" in center headwall.
- 43.62' S.E. to "+" south end conc. headwall.
- 52.89' S.W. to shiner n/s power pole.
- 29.44' S.W. to "+" west end conc. headwall.

8/7/79 R.W., J.J., G.M.

B - Found iron pipe over top center of stone (9"x10"x14") 19" below road surface. Removed iron pipe. Placed center punched RR spike on surface over top center of stone. Pk's 6' north and west. Stone is 1.0' north of south edge 18' pavement.

- 45.61' W.N.W. to shiner e/s telephone pole.
- 44.09' N. to near face wood corner post.
- 73.89' S.S.E. to NW corner house foundation.
- 46.73' S. to duplex w/s 22" maple.
- 39.78' S.W. to "+" west end RCP. (P)
- 62.69' S.W. to shiner e/s power pole.
- 7/27/88 R.W., S.K., K.A. Found baby RR spike.
- 37.80' N.E. to "+" SW corner catch basin. (P)
- 73.90' S.S.E. to NW corner house foundation.
- 46.70' S. to duplex (new) w/s maple tree.
- 39.87' S.W. to "+" west end conc. pipe. (P)
- 62.72' S.W. to shiner e/s power pole.
- 62.55' S.W. to shiner ne/s power pole.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4-N R-8-E

SECTION: 26

10/23/79 R.W., J.J., C.S.

C - Found iron pipe over top center of stone (6"x7"x12") 15" below road surface. Removed iron pipe and placed center punched RR spike on surface. Pk's 5' south and east. Stone is 4.9' east of west edge 14' pavement.

- 21.69' N.W. to SE corner north bridge rail.
- 35.37' N.E. to duplex w/s telephone pole.
- 16.44' S.E. to NW corner east bridge rail.
- 14.89' S.W. to NE corner west bridge rail.
- 35.02' S.W. to duplex n/s power pole.
- 17.11' W.S.W. to NE corner south bridge rail.

7/27/88 R.W., S.K., K.A.

- 25.10' N.W. to "+" east end conc. headwall. (P)
- 35.34' N.E. to duplex w/s telephone pole.
- 35.05' S.W. to duplex n/s power pole.
- 23.34' S.W. to "+" south end conc. headwall. (P)

10/22/79 R.W., J.J., C.S.


D - Found stone (6"x12"x13") 3" below surface. Placed 5/8"x30" iron pins 6.0' southeast and southwest. Stone is 2.2' north of south edge 11" stone road.

- 38.35' N. to "+" in conc. base for triangulation station.
- 19.88' N. to duplex w/s power pole.
- 31.94' S.E. to duplex w/s 18" catalpa.
- 27.05' S. to duplex w/s 14" catalpa.
- 57.29' W.S.W. to duplex s/s telephone pole.

7/27/88 R.W., S.K., K.A.

Placed 5/8" iron pin angled over top center of stone.

- 38.40' N. to "+" in conc. slab.
- 19.88' N. to duplex w/s power pole.
- 31.88' S.E. to duplex w/s catalpa tree.
- 27.04' S. to duplex w/s catalpa tree.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4-N R-8-E

SECTION: 27

7/26/79 R.W., J.J., G.M.

A - Found recorded iron pipe over iron pin. No stone could be located. Replaced iron pipe in original position. Pk's 6' north and west.

56.30' N.W. to duplex se/s telephone pole.

29.88' N.W. to "+" north end of headwall.

49.04' N.E. to shiner sw/s telephone pole.

50.75' N.E. to center USGS BM "B-117".

28.68' S.W. to "+" south end of headwall.

8/1/88 R.W., S.K. Found Pk. nail and shiner on surface.

41.66' N.W. to shiner se/s signal pole.

56.29' N.W. to duplex sw/s power pole.

41.61' N.W. to "+" north end conc. pipe.

50.74' N.E. to center USGS BM "B-117 1947".

48.94' N.E. to shiner sw/s telephone pole.

40.49' S.E. to shiner nw/s signal pole.

39.93' S.W. to "+" center north wall catch basin. (P)

60.40' S.W. to "+" south end conc. pipe. (P)

12/21/79 R.W., C.S.

B - Corner is lost. Reestablished N¼ Post midway between and in line with the NE corner and NW corner of Sec. 27. Placed 5/8" x 18" iron pin at N¼ Post. Pk's 15' northeast and northwest. Stone is 8.0' south of south edge 20' pavement.

43.55' N.N.E. to "+" top east end conc. headwall. (P)

52.81' N.N.E. to duplex s/s telephone pole. (P)

19.72' S.E. to 5/8"x30" iron pin on ditch bank.

22.02' S.W. to 5/8"x30" iron pin on ditch bank.


9/1/88 R.W., S.K., K.A. Reset iron pin. Set new Pk's 10' NW and NE.

36.11' N.W. to 5/8" iron pin at north edge pavement. (P)

37.58' N.E. to 5/8" iron pin at north edge pavement. (P)

19.74' S.E. to 5/8" iron pin on ditch bank. (P)

22.06' S.W. to 5/8" iron pin on ditch bank. (P)



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4-N R-8-E

SECTION: 27

8/2/79 R.W., J.J., G.M.


C - Found recorded RR spike. Searched for stone but did not locate. RR spike is midway between NW corner and SW corner, Sec. 27. Placed center punched RR spike on surface. RR spike is 7' east of west edge 18' pavement.

- 22.88' N.W. to SE corner north bridge rail.
- 79.91' N.N.E. to shiner sw/s telephone pole.
- 54.42' S.S.E. to "+" NW corner catch basin. (P)
- 83.90' S.S.E. to shiner nw/s telephone pole.
- 16.94' W.S.W. to NE corner south bridge rail.

8/1/88 R.W., S.K.

Found Pk nail and shiner.

- 22.88' N.E. to SE corner of north banister.
- 55.78' S.S.E. to "+" east end of conc. pipe. (P)
- 16.95' W.S.W. to NE corner of south banister.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4-N R-8-E

SECTION: 28

6/8/79 R.W., J.J., G.M.

A - Found RR spike over wood stake in clay tile, over small stone over cornerstone (8"x10"x12") 32" below road surface. RR spike was 0.17' west and 0.15' north of top center of stone. Removed wood stake, tile and small stone. Placed center punched RR spike on surface over high point of stone. Pk's 6' south and east.

52.39' N.W. to shiner se/s telephone pole.

34.60' N.W. to "+" NE corner conc. headwall.

70.33' N.E. to shiner sw/s telephone pole.

56.61' S.S.E. to duplex nw/s power pole.

28.89' S.W. to "+" east end conc. bridge wall.

7/1/88 R.W., S.K. Found baby RR spike.

52.44' N.W. to shiner se/s telephone pole.

34.41' N.W. to "+" north end conc. headwall. (P)

54.02' N.E. to center USGS BM "C-117 1947". (P)

68.91' E.N.E. to shiner sw/s telephone pole.

57.13' S.S.E. to shiner nw/s power pole.

29.11' S.W. to center USGS BM "C-117 RESET 1981".

6/4/79 R.W., J.J., G.M.

B - Found recorded iron pin (5/8") driven through fractured stone (4"x8"x15") 4" below ground surface. Iron pin is true point. Stone is located 4.3' west of west edge 18' pavement. Pk's 10' southeast and northeast.

88.83' S.S.E. to duplex nw/s power pole.

8.18' S.W. to "+" north end conc. headwall.


32.08' W.S.W. to duplex n/s telephone pole.

7/1/88 R.W., S.K. Found iron pin. Set Pk's 10' northeast and southeast.

88.83' S.S.E. to duplex nw/s power pole.

21.62' S.S.W. to "+" in conc. wing. (P)

8.28' S.W. to "+" in conc. wing. (P)



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4-N R-8-E

SECTION: 28

11/12/79 R.W., J.J., C.S.

C - Found recorded RR spike 0.15' south of 1x2 wood stake 24" below road surface. Placed center punched RR spike on surface over 1x2 wood stake. Pk's 6' north and west. RR spike is 5.6' north of south edge 19' pavement.

67.81' W.N.W. to shiner se/s telephone pole. GONE

39.15' N.W. to "+" in 12" RCP. (P)

42.14' N. to center USCG Sta. "BENEIN-1947". (P)

27.28' N. to "+" in 12" RCP. (P)

76.44' N.E. to shiner sw/s telephone pole. GONE

44.96' S. to shiner n/s corner post (loose).


7/1/88 R.W., S.K.

Found baby RR spike. Set Pk's 6' north and west.

39.22' N.W. to "+" west end conc. pipe. (P)

27.36' N.N.W. to "+" east end conc. pipe. (P)

42.20' N. to center Sta. "BENEIN 1947". (P)



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4-N R-8-E

SECTION: 29

6/8/79 R.W., J.J., G.M.

A - Found RR spike over high point of stone (14"x15"x15") 17" below road surface. Point falls in groove in top of stone. Found pieces of broken vitrified pipe over stone. Placed center punched RR spike on surface over high point of stone. Pk's 6' north and east.

- 52.50' N.W. to shiner se/s telephone pole.
- 52.89' N.E. to shiner sw/s corner fence post.
- 21.46' S.W. to "+" east end conc. headwall.
- 28.32' W.S.W. to "+" west end conc. headwall.
- 8/22/88 R.W., S.K., K.A. Found baby RR spike.
- 53.00' N.W. to shiner se/s telephone pole.
- 52.90' N.E. to shiner sw/s wood corner post.
- 55.93' N.E. to center USGS BM "B-117 1948".
- 21.49' S.W. to "+" east end conc. parapet.
- 28.35' W.S.W. to "+" west end conc. parapet.
- 51.48' S.W. to shiner ne/s power pole.

6/8/79 R.W., J.J., G.M.

B - Found Pk 0.10' north and 0.50' east of stone (5"x7"x24") 12" below road surface. Stone is leaning to the south. Removed Pk and placed center punched RR spike on surface over high point of stone. Pk's 6' south and west. Stone is 8.0' north of south edge 18' pavement.

- 87.09' N.N.W. to shiner se/s telephone pole.
- 39.57' N.E. to "+" west end conc. headwall.
- 85.42' E.N.E. to shiner sw/s telephone pole.
- 48.28' E.S.E. to "+" east end conc. headwall.
- 51.55' S.S.E. to shiner n/s power pole.
- 47.22' S.S.W. to center USGS Bench Mark.
- 8/24/88 R.W., K.A. Found baby RR spike. Set Pk's 6' south and west.
- 87.07' N.W. to shiner se/s telephone pole.
- 39.65' N.E. to "+" west end conc. headwall. (P)
- 85.56' E.N.E. to shiner sw/s telephone pole.
- 48.30' E.S.E. to "+" east end conc. headwall. (P)
- 37.19' E.S.E. to "+" west end conc. headwall. (P)
- 51.54' S.E. to shiner nw/s power pole.
- 47.17' S. to center Sta. "IMBROCK 1947".

A

B

C	

COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4-N R-8-E

SECTION: 29

10/29/79 R.W., J.J., C.S.

C - Found stone (6"x7"x10") 19" below grade. Found three smaller stones over true stone. Removed smaller stones. Angled 5/8"x30" iron pin over high point of stone. Pk's 6' northeast and southeast. Stone is 1.9' west of west edge 10' pavement.

21.40' N.E. to 5/8"x30" iron pin 3' east of east edge pavement.

23.88' S.E. to 5/8"x30" iron pin 3' east of east edge pavement.

50.10' S.W. to hole in top center 10" CMP. (P)

8/24/88 R.W., K.A.

21.73' N.E. to 5/8" iron pin 3' east of pavement. (RESET)

23.86' S.E. to 5/8" iron pin 3' east of pavement.

A	C
B	

COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4-N R-8-E

SECTION: 30

6/6/79 R.W., J.J., G.M.

A - Found RR spike over high point of stone (7"x8"x11") 18" below road surface. Placed center punched RR spike on surface over high point of stone. Pk's 6' south and east.

31.55' N.N.W. to "+" in base conc. bridge wall.

50.86' N.N.E. to shiner w/s telephone pole.

54.40' S.E. to shiner n/s power pole.

20.79' S.W. to "+" in base conc. bridge wall.

8/24/88 R.W., K.A. Found baby RR spike.

31.54' N.N.W. to "+" in conc. curb of banister.

50.98' N.N.E. to shiner w/s telephone pole.

51.50' N.N.E. to center USGS BM "E 117 1947". (P)

44.19' S.E. to "+" east end conc. headwall. (P)

54.42' S.E. to shiner n/s power pole.

20.81' S.W. to "+" in conc. curb of banister.

4/25/96 R.W.

25.05' S to "+" in N wing of bridge.

6/25/79 R.W., G.M.

B - Found stone (15"x19"x20") 16" below road surface. Placed center punched RR spike on surface over high point of stone. Pk's 6' northeast and southeast. Stone is 0.3' east of west edge 18' pavement.

30.61' E.S.E. to duplex n/s power pole.

37.82' S.E. to "+" NW corner catch basin. (P)

28.51' S.W. to "+" in 8" conc. pipe. (P)


43.12' N. to E¼ Post, Sec. 25, Monroe Twp.

8/24/88 R.W., K.A.

30.68' E.S.E. to duplex n/s power pole.

37.84' S.E. to "+" NW corner catch basin. (P)

28.59' S.W. to "+" west end 8" conc. pipe. (P)



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4-N R-8-E

SECTION: 30

C - Found Pk 0.70' north and 4.70' east of top center of stone. Placed center punched RR spike on surface over top center of stone. Pk's 6' north and west. Stone is 7.1' north of south edge pavement. Stone is 8"x8"x11" and 16" below road surface.

32.74' N.N.W. to "+" in center south wall catch basin. (P)

36.06' N.E. to shiner s/s telephone pole.

57.60' S.E. to shiner nw/s power pole.

35.05' S.E. to hole top center 36" CMP.

26.62' S. to "+" top center 36" CMP.

8/24/88 R.W., K.A.


Found baby RR spike.

32.76' N.N.W. to "+" center south wall catch basin. (P)

36.05' N. to shiner s/s telephone pole.

57.64' S.E. to shiner nw/s power pole.

25.48' S.S.W. to "+" south end RCP. (P)



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4-N R-8-E

SECTION: 31

8/73 H. Helberg


- A - Found stone. Placed RR spike on surface over stone. Pk's 6' north and east.
 38.82' N.N.W. to SE corner of south bridge rail.
 61.45' N.N.W. to SE corner of north bridge rail.
 46.65' N.W. to SW corner of south bridge rail.
 80.07' N.N.E. to Pk in se/s of power pole.
 42.64' N. to RR spike over Monroe Twp. stone.
 1.60' W. to west edge of pavement.

6/20/88 R.W., K.A.

- 39.19' N.N.W. to "+" top east end of banister.
 80.04' N.N.E. to Pk nail se/s power pole.
 32.03' S.E. to Pk nail east end CMP. (P)
 28.10' S.W. to Pk nail west end CMP. (P)

10/29/79 R.W., J.J., C.S.

- B - Found stone (10"x13"x16") 8" below grade on north bank of road ditch. Angled 5/8"x30" iron pin on ne/s of stone. Top of iron pin is over high point of stone. Pk's 10' northwest and northeast. Stone is 7.2' south of south edge of 18' pavement.
 28.07' N.N.E. to SE corner conc. catch basin. (P)
 3.03' S.E. to "+" in 10" conc. pipe. (P)
 16.77' S.W. to 5/8"x30" iron pin on south bank of ditch.
 37.50' E. to 5/8"x30" iron pin.
 6/20/88 R.W., K.A.
 28.09' N. to "+" SE corner catch basin. (P)
 31.97' N.E. to 5/8" iron pin 1' north of pavement. (P)
 3.04' S.E. to "+" south end conc. pipe. (P)
 16.55' S.W. to 5/8" iron pin on south ditch bank. (P)



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4-N R-8-E

SECTION: 31

B1 - Found stone (3"x5"x10") 4" below grade on north ditch bank. High point of stone is 0.45' south of North Line of Sec. 31. Placed 5/8"x 30" iron pin on North Line of Sec. 31 due north of high point of stone. Pk's 10" northwest and northeast. Stone is 7.3' south of south edge 18' pavement.

- 44.23' W.N.W. to SE corner conc. catch basin.(P)
- 34.41' W.S.W. to "+" in top of 10" conc. pipe. (P)
- 37.50' W. to N¼ Post, Sec. 31.


- 6/20/88 R.W., K.A.
- 44.28' W.N.W. to "+" SE corner catch basin. (P)
- 33.83' N.W. to 5/8" iron pin 1' north of pavement. (P)
- 51.75' W.S.W. to 5/8" iron pin on south ditch bank.
- 35.42' W. to "+" south end conc. pipe.

C - Found stone (11"x14"x14") 9" below road surface. High point of stone is 0.30' east of East Line, Sec. 36, Monroe Twp. Placed center punched RR spike on East Line, Sec. 36, Monroe Twp., 0.30' west of high point of stone. Pk's 6' north and west. Stone is 5.4' west of east edge 16' pavement.

- 43.92' N.W. to duplex s/s 8" elm.
- 23.10' N.E. to duplex n/s power pole.
- 21.40' N. to E¼ Post, Sec. 36, Monroe Twp.
- 66.49' S.S.W. to "+" top north end conc. headwall. (P)

- 6/28/88 R.W., K.A.
- 43.65' N.W. to Pk nail s/s 12" elm. NEW
- 23.15' N.E. to duplex n/s power pole.
- 66.09' S.S.E. to "+" NW corner catch basin.
- 66.52' S.S.W. to "+" north end conc. headwall. (P)

D - See SE Corner, Sec. 36, Monroe Twp.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4-N R-8-E

SECTION: 31

11/2/79 R.W., J.J., C.S.


E - 1905 Survey. Found stone (8"x10"x18") 10" below road surface. Placed center punched RR spike on surface over high point of stone. Pk's 6' north and west. Stone is 7.1' north of south edge of 18' pavement.

- 109.88' W.N.W. to duplex s/s telephone pole.
- 36.80' N.E. to duplex se/s telephone pole.
- 45.77' S.E. to near face iron corner post.
- 51.78' S.W. to duplex n/s power pole.
- 32.34' E. to N¼ Post, Sec. 6, Bartlow Twp.
- 7/88 R.W., S.K., K.A.
- 36.53' N.E. to duplex (new) nw/s telephone pole.
- 45.82' S.E. to "+" n/s iron corner post.
- 26.75' S.E. to Pk nail south end CMP. (P)
- 51.60' S.W. to duplex nw/s power pole.
- 39.85' E. to Stone (1907 Survey).

11/6/79 R.W., J.J., C.S.

E1 - 1907 Survey. Found stone (3"x6"x16") 10" below road surface. Placed center punched RR spike on South Line, Sec. 31. RR spike is 0.15' south of top center of stone. Pk's 6' north and east. Stone is 7.4' north of south edge 18' pavement.

- 29.20' N.N.W. to duplex se/s telephone pole.
- 33.46' S.S.W. to near face iron corner post.
- 85.26' W.S.W. to duplex n/s power pole.
- 39.84' W. to S¼ Post, Sec. 31, Richfield Twp.
- 7.50' W. to N¼ Post, Sec. 6, Bartlow Twp.
- 7/88 R.W., S.K., K.A.
- 29.28' N.W. to duplex se/s telephone pole.
- 19.04' N.E. to 5/8" iron pin 2' north of pavement.
- 33.50' S.S.W. to "+" n/s iron corner post.
- 31.77' S.W. to Pk nail south end CMP. (P)
- 85.17' W.S.W. to duplex nw/s power pole.
- 39.85' W. to Stone (1905 Survey).



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4-N R-8-E

SECTION: 32

8/73 H. Helberg

A - Found stone with old stake beside and VSP over. Placed 1/2"x17" pipe over stone. Found small stone 10" north and 6" higher, removed it. Also found iron pin over nothing and removed.

New ties: 10/5/79 Pk's 6' north and east.

29.42' S.E. to "+" with drill hole south end headwall.

24.83' S.W. to "+" with drill hole south end headwall.

59.61' W.S.W. to duplex nw/s telephone pole.

44.93' W.N.W. to Pk nail sw/s power pole.

6/27/88 R.W., K.A. Found iron pipe and Pk's

44.77' N.W. to Pk nail sw/s power pole.

24.52' N.W. to "+" in NE wingwall. (P)

51.27' N.E. to "+" NE corner conc. slab. (P)

29.47' S.E. to "+" south end conc. headwall. (P)

24.94' S.W. to "+" south end conc. headwall. (P)

18.53' S.W. to "+" center SE wingwall. (P)

10/5/79 R.W., C.S.

B - Found recorded 1/2" iron pipe over high point of stone. Found hinge nails 6' northwest and northeast. Stone is 4"x9"x14" and 9" below edge of pavement.

24.45' N. to duplex e/s 8" tree.

27.83' N. to iron pipe. (P)

58.47' S.E. to hinge nail s/s twin maples.

20.35' S. to near face steel fence post.


6/27/88 R.W., K.A.

25.05' N.W. to 5/8" iron pin 1' north of pavement.

24.36' N. to duplex e/s 12" tree.

27.86' N. to center of iron pie. (P)

26.73' N.E. to 5/8" iron pin 1' north of pavement.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4-N R-8-E

SECTION: 32

10/5/79 R.W., J.J.

C - Found recorded harrow tooth 0.25' west of high point of stone (9"x11"x14") 19" below road surface. Found clay tile over stone. Re-set harrow tooth with center punched hole on surface over high point of stone. Pk's 6' northeast and southeast. Stone is 1.1' east of west edge 12' pavement.

- 34.48' W.S.W. to duplex ns/ power pole
- 29.03' E. to nail/shiner s/s 10" corner post.
- 29.16' S.S.E. to "+" south end of east wall of catch basin. (P)
- 51.95' S.E. to duplex w/s telephone pole. GONE
- 21.49' S.W. to rivet west end 15" CMP. (P)


6/27/88 R.W., K.A.

- 29.05' E. to nail/shiner s/s wood corner post.
- 29.13' S.E. to "+" south end; east wall of catch basin. (P)
- 21.53' S.W. to rivet top west end CMP. (P)
- 34.45' W.S.W. duplex n/s power pole.

10/31/79 R.W., J.J., C.S.

D - Searched for stone. Did not locate. Reestablished Southwest Corner of section from witness ties to bridge rails. Placed center punched RR spike on surface. Pk's 6' north and west. RR spike is 5.7' north of south edge pavement.

- 21.30' N.W. to SE corner bridge rail.
 - 65.07' E.N.E. to duplex nw/s telephone pole.
 - 32.62" E. to NW Corner, Sec. 5, Bartlow Twp.
 - 40.24' S.W. To duplex se/s power pole.
 - 16.40' W.S.W. to NE corner bridge rail.
- 6/20/88 R.W., S.K, K.A.
- 22.01' N.W. to "+" in NW wingwall. (P)
 - 64.89' N.E. to "+" in SE corner catch basin. (P)
 - 65.08' E.N.E. to duplex nw/s telephone pole. NEW
 - 62.04' E.S.E. to "+" south end conc. headwall. (P)
 - 12.66' S.W. to "+" in SE wingwall. (P)



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4-N R-8-E

SECTION: 32


11/6/79

E - Found stone (9"x10"x12") 15" below road surface. Stone is badly fractured. Placed center punched RR spike on surface over top center of stone. Pk's 6' north and west. Stone is 6.9' north of south edge 18' pavement.

- 56.22' W.N.W. to duplex s/s telephone pole.
- 24.75' N. to "+" on high point of witness stone.
- 84.76' E.N.E. to duplex s/s telephone pole.
- 70.55' E.S.E. to duplex n/s power pole.
- 26.53' E. to N¼ Post, Sec. 5, Bartlow Twp.

6/20/88 R.W., S.K., K.A.

- 56.24' W.N.W. to duplex s/s telephone pole.
- 25.02' N.W. to Pk west end CMP. (P)
- 24.78' N. to "+" on high point of witness stone.
- 18.73' N. to Pk east end CMP. (P)
- 84.63' E.N.E. to duplex s/s telephone pole.
- 70.48' E.S.E. to duplex n/s power pole.



COUNTY: HENRY
 TOWNSHIP: RICHFIELD
 T-4-N R-8-E
 SECTION: 33

9/28/79 R.W., J.J., C.S.

A - Found recorded RR spike over top center of stone (7"x8"x5") 13" below road surface. Placed center punched RR spike on surface over top center of stone. Pk's 6' north and west. Stone is 1.3' east of west edge 14' pavement.

- 25.39' N.W. to "+" top NE bridge wingwall. (P)
- 45.34' N.W. to duplex ne/s telephone pole.
- 37.38' N.E. to hinge nail s/s power pole.
- 33.93' S.E. to "+" top east end 36" RCP. (P)
- 17.81' S.W. to "+" top SE bridge wingwall.

6/27/88 R.W., K.A.

- 44.68' N.W. to duplex s/s telephone pole.
- 22.23' N.W. to SE corner of north banister.
- 36.84' N.E. to duplex s/s telephone pole.
- 33.86' S.E. to "+" east end conc. pipe. (P)
- 17.89' S.W. to "+" south end SE wingwall. (P)


10/3/79 R.W., J.J., C.S.

B - Found stone (9"x15"x17") 10" below road surface. Placed center punched on surface on the North Line of Sec. 33. Pk's 6' northwest and northeast. RR spike is 1.13' north of high point of stone. Stone is 2' north of south edge 14' pavement. RR spike is 3.1' north of south edge.

- 18.31' N.W. to 5/8" iron pin at north edge pavement.
- 18.20' N.E. to 1/2" iron pipe at north edge pavement.
- 13.58' E.S.E. to 5/8" iron pin at south edge pavement.
- 108.40' E. to N¼ Post, Sec. 33.

6/27/88 R.W., K.A.

- 18.42' N.W. to 5/8" iron pin at north edge pavement.
- 18.17' N.E. to 5/8" iron pin at north edge pavement.
- 13.53' E.S.E. to 5/8" iron pin at south edge pavement.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4-N R-8-E

SECTION: 33

10/3/79 R.W., J.J., C.S.

C - Found stone (7"x8"x11") 14" below road surface with clay tile over top of stone. Stone is fractured. Placed center punched RR spike on surface over top center of stone. Pk's 6' northwest and northeast. Stone is 2.2' north of south edge 14' pavement. Found nail/shiner 5.3' north and 2.35' east. Removed nail/shiner.

24.93' N.N.W. to 16d spike s/s wood anchor post.
 18.62' N.N.E. to 1" iron pipe at north edge pavement.
 12.96' E.S.E. to 5/8" iron pin at south edge pavement.

6/27/88 R.W., K.A.

18.72' N.E. to 1" iron pipe 1' north of pavement.
 12.97' E.S.E. to 5/8" iron pin 1' south of pavement.
 9.12' W.S.W. to 5/8" iron pin 1' south of pavement.


11/21/79 R.W., J.J., C.S.

D - Found stone (7"x10"x8") 18" below road surface. Placed center punched RR spike on surface over high point of stone. Pk's 6' north and west. Stone is 5.8' west of east edge 16' pavement.

37.86' W. to near face 2" iron pipe. (loose)
 87.22' N.N.W. to duplex e/s telephone pole.
 71.42' S.S.E. to duplex w/s power pole.
 110.37' S.S.W. to duplex e/s telephone pole.

6/27/88 R.W., K.A.

15.47' N.W. to 5/8" iron pin 1' west of pavement.
 12.96' N.E. to 5/8" iron pin 1' east of pavement.
 71.41' S.S.E. to duplex w/s power pole.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4-N R-8-E

SECTION: 33

10/31/79 R.W., J.J., C.S.

E - Found recorded RR spike over stone (10"x14"x10") 12" below road surface. Placed center punched RR spike on surface over stone. Pk's 6' south and west. Stone is 7.7' south of north edge 18' pavement.

40.47' W.N.W. to "+" top east end conc. bridge rail.

55.06' N.E. to duplex s/s power pole.

55.04' E.S.E. to duplex sw/s power pole.

72.30' S. to duplex e/s 10" maple.

6/20/88 R.W., S.K., K.A.

40.45' W.N.W. to "+" east end conc. banister.

54.76' N.E. to duplex s/s power pole. NEW

57.50' E.S.E. to "+" east end conc. pipe. (P)

55.02' E.S.E. to duplex sw/s power pole.

19.92' E. to NW Corner, Sec. 5, Bartlow Twp.

72.30' S. to duplex e/s maple.

11/8/79 R.W., J.J., C.S.

F - No record of stone being set. Searched for a stone, did not locate. Reestablished S¼ Post midway between the SW corner and the SE corner of Sec. 33. Placed center punched RR spike on surface. Pk's 6' south and west. Stone is 6.4' south of north edge 18' pavement.

95.12' W.N.W. to duplex s/s telephone pole. GONE

56.83' E.N.E. to duplex s/s telephone pole. GONE

60.87' E.S.E. to duplex n/s power pole.


17.36' E. to N¼ Post, Sec. 4, Bartlow Twp.

6/27/88 R.W., K.A.

9.68' N.W. to 5/8" iron pin 0.5' north of pavement.

24.77' N.E. to 5/8" iron pin 0.5' north of pavement.

60.78' E.S.E. to duplex n/s power pole.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4-N R-8-E

SECTION: 34

8/1/79 R.W., J.J., C.S.

A - Found recorded iron pipe over top center of stone (10"x10"x7") 12" below road surface. Removed iron pipe. Placed center punched RR spike on surface over top center of stone. Pk's 6' north and west. Stone is 8.2' east of west edge 18' pavement.

41.85' N.W. to shiner se/s power pole.

42.34' N.E. to iron pin.

51.51' E.N.E. to shiner w/s 24" walnut. GONE

96.59' N.N.E. to shiner s/s telephone pole.

20.74' S.E. to NW corner conc. bridge rail. GONE

91.64' S.S.E. to shiner nw/s 14" walnut.

7/24/88 R.W., K.A. Found Pk nail and shiner.

41.82' N.W. to shiner se/s power pole.

51.41' N.E. to shiner sw/s walnut tree.

34.72' S.E. to "+" east end RCP. (P)

28.85' S.W. to "+" west end RCP. (P)

10/26/79 R.W., J.J., C.S.

B - Found stone (6"x17"x19") 10" below grade. Found iron pipe 4.3' east and 1.1' south of stone. Removed iron pipe. Placed center punched RR spike on surface over high point of stone. Pk's 6' north and east. Stone is 2.5' north of south edge 16' pavement.

21.99' N.E. to 5/8" iron pin at north edge of pavement.


22.32' N.E. to 5/8" iron pin at north edge of pavement.

55.00' S.E. to duplex n/s clump of 8" walnut trees. GONE

8/24/88 R.W., S.K.

21.99' N.W. to 5/8" iron pin 1' north of edge of pavement.

22.34' N.E. to 5/8" iron pin 1' north of edge of pavement.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4-N R-8-E

SECTION: 34

8/6/79 R.W., J.J., C.S.

C - Found recorded spike 1" below road surface. RR spike established by ODOT. Spike is on line and midway between SW Corner and NW Corner, Sec. 34.

- 18.13' W. to NE corner west bridge rail.
- 62.64' N.N.W. to shiner se/s power pole.
- 80.98' N.N.E. to shiner sw/s telephone pole.
- 18.22' E. to NW corner east bridge rail.
- 20.75' S.E. to SW corner east bridge rail.
- 70.88' S.S.E. to shiner nw/s telephone pole.
- 20.70' S.W. to SE corner west bridge rail.

8/24/88 R.W., S.K. Found baby RR spike.

- 19.88' N.W. to "+" NW wingwall. (P)
- 48.66' N.E. to duplex nw/s power pole.
- 19.29' E.N.E. to "+" NE wingwall. (P)
- 25.13' S.E. to "+" SE wingwall. (P)
- 25.10' S.W. to "+" SW wingwall. (P)


8/2/79 R.W., J.J., G.M.

D - Found recorded RR spike over high point of stone (6"x10"x16") 15" below road surface. Also found wood stake on se/s stone and several small stones. Removed wood stake and small stones. Placed center punched RR spike on surface over high point of stone. Pk's 6' north and west. Stone is on the west edge 18' pavement.

- 45.85' S.S.W. to duplex e/s power pole.
- 57.24' N.N.W. to duplex e/s power pole.
- 88.81' N.E. to shiner sw/s telephone pole.
- 72.90' E.S.E. to duplex n/s power pole.
- 17.72' E. to NW corner, Sec. 3, Bartlow Twp.

8/24/88 R.W., S.K. Found Pk nail and shiner.

- 29.70' N.W. to "+" SE corner metal frame of catch basin grate. (P)
- 57.17' N.W. to duplex e/s power pole.
- 87.16' E.N.E. to shiner w/s telephone pole.
- 72.91' E.S.E. to duplex/s power pole.
- 35.38' S.W. to "+" SW corner catch basin. (P)



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4-N R-8-E

SECTION: 34

11/14/79 R.W., J.J., C.S.

E - Searched for stone, did not locate. Reestablished $S\frac{1}{4}$ Post by single proportionate measurement along the South Line of Sec. 34, between the SE Corner and SW Corner of Sec. 34. Placed center punched RR spike on surface. Pk's 6' north and west. RR spike is 2' north of south edge 18' pavement.

27.94' N. to duplex e/s telephone pole.


27.55' S.S.W. to duplex e/s power pole.

16.54' E. to $N\frac{1}{4}$ Post, Sec. 3, Bartlow Twp.

8/24/88 R.W., K.A.

30.36' N. to nail/shiner e/s telephone pole. NEW

27.54' S.S.W. to duplex e/s power pole.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4-N R-8-E

SECTION: 35

10/24/79 R.W., J.J., C.S.

A - Found stone (5"x7"x24") in a horizontal position over 1-1/8" iron bar. Iron bar is 17" below road surface. Placed center punched RR spike on surface over iron bar. Iron bar is 3.5' north of south edge 18' pavement. Pk's 6' north and east.

8/12/05 R.W., S.K.

Small RR spike on surface

40.32' S.E. to sawed "+" east end of RCP

38.63' S.W. to sawed "+" west end of RCP

38.45' N.E. to duplex se/side of power pole

10/26/79 R.W., J.J., C.S.

B - Found stone (6"x8"x10") 14" below grade. Placed 5/8"x30" iron pin on n/s stone with top of iron pin over high point of stone. Pk's 6' northeast and northwest. Stone is 2.3' south of south edge 12' pavement.

93.81' W.N.W. to SE corner brick column. (P)

50.79' N.W. to duplex ne/s 15" pear tree. (P)

32.58' N. to near face of iron pipe. (P)

131.63' E.N.E. to duplex s/s power pole. (P)


8/25/88 R.W., S.K., D.H.

93.80' W.N.W. to SE corner brick column. (P)

50.81' N.W. to duplex e/s pear tree.

32.58' N. to near face 4" iron pipe.

25.67' S. to Pk nail w/s 6" oak tree.



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4-N R-8-E

SECTION: 35

10/25/79 R.W., J.J., C.S.

C - Found recorded iron pin 0.25' south of high point of stone (4"x7"x8") 17" below road surface. Removed iron pin. Placed center punched RR spike on surface over high point of stone. Pk's 6' north and east. Stone is 2.0' east of west edge of 18' pavement.
 15.47' N.N.W. to 5/8"x30" iron pin at west edge of pavement.

21.53' E. to duplex s/s wood anchor post.

17.12' S.S.W. to 5/8"x30" iron pin at west edge of pavement.

8/25/88 R.W., S.K., K.A. Found RR spike, also Pk's north and east.

15.45' N.N.W. to 5/8" iron pin 0.5' west of pavement.

17.47' E. to 5/8" iron pin 1' east of pavement.

17.12' S.S.W. to 5/8" iron pin 1' west of pavement.

11/13/79 R.W., J.J., C.S.

D - Found recorded iron pin 0.30' north of top center of stone (7"x9"x7") 17" below road surface. Removed iron pin. Placed center punched RR spike on surface over top center of stone. Pk's 6' north and west. Stone is 6.7' north of south edge 18' pavement and 7.0' west of west edge 18' pavement (looking south).

47.60' W.N.W. to duplex s/s telephone pole.

75.66 N.N.E. to duplex w/s telephone pole.

84.64' E.N.E. to duplex s/s telephone pole.

53.88' E.S.E. to duplex n/s power pole.

30.55' S.S.W. to duplex e/s brace pole.

17.16' E. to NW corner, Sec. 2, Bartlow Twp.


8/25/88 R.W., S.K., D.H. Found RR spike.

37.68' N.W. to duplex ne/s telephone pole. NEW

84.57' E.N.E. to duplex s/s telephone pole.

53.87' S.E. to duplex n/s power pole.

31.57' S.S.W. to duplex w/s brace pole. NEW



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4-N R-8-E


SECTION: 35

11/16/79 R.W., J.J., C.S.

E - Found stone (7"x12"x13") 15" below road surface. Placed center punched RR spike on surface over top center of stone. Pk's 6' north and west. Stone is 7.2' north of south edge 18' pavement.

- 24.80' N.N.E. to duplex e/s telephone pole.
- 69.13' E.N.E. to SW corner curb of bridge rail (P)
- 46.10' E.S.E. to NW corner curb of bridge rail. (P)
- 36.50' S.W. to "+" top 24" CMP.
- 20.80' E. to N¼ Post, Sec. 2, Bartlow Twp.

8/25/88 R.W., S.K., D.H. Found RR spike.
 24.85' N.N.W. to duplex e/s telephone pole.
 69.13' E.N.E. to SW corner curb of bridge banister.



COUNTY: HENRY
 TOWNSHIP: RICHFIELD
 T-4-N R-8-E
 SECTION: 36

10/19/79 R.W., C.S.

A - Found recorded iron pin 0.25' north of top center of stone (4"x10"x13") 12" below road surface. Removed iron pin. Placed center punched RR spike on surface over top center of stone. Pk's 6' north and east. Stone is 4.5' east of west edge 18' pavement.

18.44' N.W. to "+" top east end conc. headwall.

35.82' N.W. to Pk in power pole.

39.49' N.E. to Pk in telephone pole. GONE

16.81' S.W. to "+" top east end conc. headwall.

8/25/88 R.W., S.K., K.A. Found RR spike.

35.77' N.W. to Pk nail ne/s power pole.

18.46' N.W. to "+" east end conc. headwall. (P)

41.02' N.E. to duplex se/s telephone pole. NEW

16.84' S.W. to "+" east end conc. headwall. (P)

10/19/79 R.W., C.S.

B - Found recorded iron pin over high point of stone (4"x6"x16") 8" below road surface. Top half of stone is loose and sits on bottom half. Found wood stake on n/s stone. Removed iron pin. Placed center punched RR spike on surface over high point of stone. Pk's 6' north and west. Stone is 5.9' north of south edge 14' pavement.

6/29/86 R.W., S.K.

Replaced stone after culvert removal. Placed center punched RR spike on surface. Pk's 6' northeast and southeast.

26.43' S.S.W. to "+" south end of 66" RCP. (P)

30.13' N.N.W. to "+" north end of 66" RCP. (P)


8/25/88 R.W., S.K. Found RR spike.

30.13' N.N.W. to "+" north end RCP. (P)

16.87' N.E. to 5/8" iron pin at north edge pavement.

15.55' S.E. to 5/8" iron pin at south edge pavement.

26.40' S.S.W. to "+" south end RCP. (P)



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4-N R-8-E

SECTION: 36

10/17/79 R.W., C.S.

C - Found iron pipe over high point of stone (5"x6"x11") 13" below road surface. Removed iron pipe. Placed center punched RR spike on surface over high point of stone. Pk's 6' south and west. Stone is 3.0' west of west edge of pavement and 9.6' north of south edge 14' pavement.

- 13.35' N.W. to SE corner north bridge rail.
- 37.96' N.W. to duplex ne/s power pole. GONE
- 50.03' N.E. to "+" top east end 24" CMP. (P)
- 36.53' S.E. to shiner n/s telephone pole. GONE
- 16.25' S.W. to NE corner south bridge rail.
- 49.17' W.S.W. to duplex n/s telephone pole. GONE
- 50.16' N. to NW Corner, Sec. 31, Milton Twp., Wood Co.


8/25/88 R.W., S.K., K.A.

- 13.31' N.W. to duplex ne/s power pole. NEW
- 39.05' N.W. to SE corner bridge rail.
- 50.05' N.E. to "+" east end RCP. (P)
- 36.62' S.E. to nail/shiner n/s buried cable marker.
- 16.23' S.W. to NE corner bridge rail.

10/24/79 R.W., J.J., C.S.

D - Found recorded iron pin 0.15' north of high point of stone (4"x10"x11") 15" below road surface. Removed iron pin. Placed center punched RR spike on surface over high point of stone. Pk's 6' north and east. Stone is 2.0' east of west edge 18' pavement.

- 63.13' N.N.W. to duplex ne/s power pole.
 - 33.98' N.E. to duplex w/s telephone pole.
 - 26.21' E. to duplex n/s wood corner post.
- 8/29/88 R.W., K.A.
- 63.03' N.N.W. to duplex ne/s power pole.
 - 34.43' N.E. to duplex w/s telephone pole.
 - 26.39' E. to duplex n/s corner post.
 - 38.85' S.E. to "+" NE corner catch basin. (P)



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4-N R-8-E

SECTION: 36

10/18/79 R.W., C.S.

E - Searched for stone. Did not locate. Reestablished E $\frac{1}{4}$ Post at recorded offset of 25.10' south of stone at W $\frac{1}{4}$ Post, Sec. 31, Milton Twp., Wood Co. Placed 5/8"x30" iron pin on line between W $\frac{1}{4}$ Post, Sec. 31, Milton Twp. and the SE corner, Sec. 36, Richfield Twp. Pk's 12' northeast and southeast. Iron pin is 6.5' west of west edge 16' pavement.

50.73' W.N.W. to 5/8"x30" iron pin at top west ditch bank. (P)

52.45' N.N.E. to 5/8"x30" iron pin at east edge 16' pavement. (P)

24.38' E. to 3/4" x 23" iron pipe at east edge 16' pavement. (P)

29.42' S.W. to 5/8"x30" iron pin at top west ditch bank.

25.10' N to W $\frac{1}{4}$ Post, Sec. 31, Milton Twp., Wood Co.

8/25/88 R.W., S.K., D.H. Found iron pin, also Pk's 12' northeast and southeast.

50.70' N.W. to 5/8" iron pin on west ditch bank.

24.84' E. to 5/8" iron pin at east edge pavement.

29.23' S.W. to 5/8" iron pin on west ditch bank.

11/14/79 R.W., J.J., C.S.

F - Found iron pin over high point of stone (10"x11"x19") 11" below road surface. Removed iron pin. Placed center punched RR spike on surface over high point of stone. Pk's 6' north and east. Stone is 2.0' east of west edge 18' pavement. and 7.7' north of south edge 18' pavement.

37.72' N.W. to Pk nail sw/s power pole.

31.42' N.W. to "+" north end 66" CMP. (P)

38.22' N.E. to duplex w/s telephone pole.

103.90' N.E. to SW corner brick veneer house.

30.42' S.W. to Pk nail south end 66" CMP. (P)

10.56' E. to NW corner, Sec. 1, Bartlow Twp.

8/29/88 R.W., K.A.


37.71' N.W. to duplex sw/s power pole.

31.40' N.W. to "+" north end CMP. (P)

38.42' N.E. to duplex w/s telephone pole.

39.27' S.E. to duplex ne/s telephone pole. NEW

30.43' S.W. to Pk nail south end CMP. (P)



COUNTY: HENRY

TOWNSHIP: RICHFIELD

T-4-N R-8-E

SECTION: 36

11/19/79 J.J., C.S.

G - No record of stone being set. Established $S\frac{1}{4}$ Post midway between the SW corner and the SE corner of Sec. 36. Placed center punched RR spike on surface. Pk's 6' north and west. RR spike is 1.0' north of south edge 12' pavement.

66.23' W.N.W. to duplex s/s power pole.

16.61' N.N.W. to SE corner bridge rail.

6.56' S.W. to NE corner bridge rail.

65.60' W.S.W. to duplex n/s power pole.

5.28' E. to $N\frac{1}{4}$ Post, Sec. 1, Bartlow Twp.

8/29/88 R.W., K.A.

68.60' W.N.W. to duplex ne/s power pole.

26.38' N.W. to $\frac{5}{8}$ " iron pin 1' north of pavement.

26.09' N.N.W. to "+" in center of conc. headwall. (P)

19.69' N.E. to $\frac{5}{8}$ " iron pin 1' north of pavement.

17.97' S.S.W. to "+" in center of conc. headwall. (P)

10/18/79 R.W., C.S.

H - Found recorded iron pin over high point of stone (12"x13"x9") 15" below road surface. Removed iron pin. Placed center punched RR spike on surface over high point of stone. Pk's 6' north and east. Stone is 1.9' east of west edge 18' pavement.

19.28' N.W. to "+" top east end of north conc. bridge rail (P)

33.13' N.E. to duplex w/s power pole.

28.23' S.E. to "+" top south end of conc. headwall (P)

23.40' S.W. to "+" top south end of conc. wingwall. (P)

8/29/88 R.W., K.A.

19.30' N.W. to "+" (damaged) east end conc. bridge curb. (P)

40.82' N.E. to duplex nw/s power pole. NEW

28.24' S.E. to "+" south end conc. headwall.

23.46' S.W. to "+" south end conc. headwall.