



Henry County, Ohio

Office of The Engineer

1823 Oakwood Ave.

Napoleon, OH 43545

Henry County Engineer: Timothy J. Schumm, P.E., P.S.

Telephone: (419) 592-2976 Email: hce@henrycountyohio.com

www.henrycountyengineer.com

Memorandum

To: Pleasant Township Bidders

From: Nick Rettig

cc: Tim Schumm- HCE

Date: May 12, 2020

Subject: Addendum 2- Pleasant Township Road Project

To All,

This is a clarification on Contract B: Resurfacing items. Reference #2, Item 823 should be 187 C.Y. based on 1.5" average depth. The quantity number now is for 2" average depth.

Thanks,

Nick Rettig

Road Bidding Blank- Contract B

To: Board of Trustees

Pleasant Township Road Project
Henry County, Ohio

May 18, 2020 at 7:00 PM

Twp. Rd. B2 (Co. Rd. 17B To Co. Rd. 17)

Length: 2647 Feet or 0.5 Mile(s)

Width: 15 Feet (Approx. 4470 S.Y. including radius and driveway work)

Type: Resurfacing with ODOT Supplement Spec: 823 (Type 1) Surface Course with Item 617 berm in place

<u>Ref. #</u>	<u>Item</u>	<u>Quantity</u>	<u>Unit</u>	<u>Description</u>	<u>Unit Price</u>	<u>Total Price</u>
1	407	225	Gal	Bituminous Tack Coat applied at 0.05 gallons per square yard	\$ _____	\$ _____
2	823	187	C.Y.	Asphalt concrete surface course PG 64-22, Type 1 (448) applied, spread and compacted at the average depth of 1.5 inches	\$ _____	\$ _____
3	617	37	C.Y.	Stabilized crushed aggregate berm in place and compacted at the average depth of 1.5 inches	\$ _____	\$ _____
4	Spec.	3	EA	Formed Construction Joint (160 L.F.)	\$ _____	\$ _____
5	614	1	L.S.	Maintaining Traffic	\$ _____	\$ _____
6	624	1	L.S.	Mobilization	\$ _____	\$ _____
7	103.05	1	L.S.	Contract Performance & Payment Bond	\$ _____	\$ _____
Total Bid					\$ _____	\$ _____