Bid Tab

Township Road 15 From County Road K to Butt Joint South of County Road Z
Length: 4765 Feet or 0.9 Mile(s)
Width: 10 Feet (Approx. 5365 S.Y. including radius and driveway work)
Type: ODOT Spec 448 W/ 617 Berm @ 1.5 Feet Wide Each Side

					Engineer's Estimate		Helms & Sons Excavating, Inc		Gerken Asphalt Paving, Inc		Henry W. Bergman, Inc	
Ref. #	Item	Quantity	Unit	Description	Unit Price	Total Price	Unit Price	Total Price	Unit Price	Total Price	Unit Price	Total Price
1	407	270	Gal	Bituminous Tack Coat applied at 0.05 gallons per square yard	$ 2.50	$ 675.00	$ 2.15	$ 580.50	$ 2.00	$ 540.00	$ 3.00	$ 810.00
2	441	224	C.Y.	Asphalt concrete surface course PG 64-22, Type 1 (448) applied, spread and compacted at the average depth of 1.5 inches	$ 175.00	$ 39,200.00	$ 180.25	$ 40,376.00	$ 177.00	$ 39,648.00	$ 200.00	$ 44,800.00
3	617	67	C.Y.	Stabilized crushed aggregate berm in place and compacted at the average depth of 1.5 inches	$ 60.00	$ 4,020.00	$ 55.00	$ 3,685.00	$ 70.00	$ 4,690.00	$ 50.00	$ 3,350.00
4	Spec.	2	EA	Formed Construction Joint (L.F.)	$ 1,000.00	$ 2,000.00	$ 700.00	$ 1,400.00	$ 800.00	$ 1,600.00	$ 200.00	$ 400.00
5	614	1	L.S.	Maintaining Traffic	$ 1,640.00	$ 1,640.00	$ 725.00	$ 725.00	$ 950.00	$ 950.00	$ 1,500.00	$ 1,500.00
6	624	1	L.S.	Mobilization	$ 2,000.00	$ 2,000.00	$ 1,000.00	$ 1,000.00	$ 1,500.00	$ 1,500.00	$ 1,500.00	$ 1,500.00
7	103.05	1	L.S.	Contract Performance & Payment Bond	$ 965.00	$ 965.00	$ 1.00	$ 1.00	$ 250.00	$ 250.00	$ 500.00	$ 500.00
				Total		**$ 50,500.00**		**$ 47,767.50**		**$ 49,178.00**		**$ 52,860.00**

Total Entire Bid **$ 50,500.00** **$ 47,767.50** **$ 49,178.00** **$ 52,860.00**

Gerken Asphalt Paving, Inc. was awarded the project