Bid Tab

(Richfield Township) Township Road 3 From County Road G to Township Road H
Length: 5290 Feet or 1 Mile(s)
Width: 18 Feet (Approx. 10650 S.Y. including radius and driveway work)
Type: Chip Seal, 1997 ODOT Spec 409 W/ Fog Seal

					Engineer's Estimate		Ward Construction Co.		Henry W. Bergman, Inc.	
Ref. #	Item	Quantity	Unit	Description	Unit Price	Total Price	Unit Price	Total Price	Unit Price	Total Price
1	409	4265	Gal	Seal coat, bituminous material (MWS 90) applied at 0.4 gallons per square yard	$ 2.50	$ 10,662.50	$ 2.60	$ 11,089.00	$ 2.10	$ 8,956.50
2	409	110	C.Y.	Seal Coat, aggregate No. 9 (washed), applied and compacted at 24 lbs per square yard	$ 32.00	$ 3,520.00	$ 26.00	$ 2,860.00	$ 25.00	$ 2,750.00
3	Spec.	1335	Gal	Fog Seal, SS-1H Dilute 50/50, Applied at 0.10-0.15 gal per square yard	$ 3.50	$ 4,672.50	$ 2.60	$ 3,471.00	$ 2.10	$ 2,803.50
4	614	1	L.S.	Maintaining Traffic	$ 400.00	$ 400.00	$ 500.00	$ 500.00	$ 500.00	$ 500.00
5	624	1	L.S.	Mobilization	$ 500.00	$ 500.00	$ 500.00	$ 500.00	$ 1,200.00	$ 1,200.00
6	103.05	1	L.S.	Contract Performance & Payment Bond	$ 245.00	$ 245.00	$ 300.00	$ 300.00	$ 200.00	$ 200.00
				Estimate Total		**$ 20,000.00**		**$ 18,720.00**		**$ 16,410.00**

(Richfield Township) Township Road 3 From State Route 281 to Township Road H
Length: 5260 Feet or 1 Mile(s)
Width: 18 Feet (Approx. 10610 S.Y. including radius and driveway work)
Type: Chip Seal, 1997 ODOT Spec 409 W/ Fog Seal

					Engineer's Estimate		Ward Construction Co.		Henry W. Bergman, Inc.	
Ref. #	Item	Quantity	Unit	Description	Unit Price	Total Price	Unit Price	Total Price	Unit Price	Total Price
1	409	4245	Gal	Seal coat, bituminous material (MWS 90) applied at 0.4 gallons per square yard	$ 2.50	$ 10,612.50	$ 2.60	$ 11,037.00	$ 2.10	$ 8,914.50
2	409	110	C.Y.	Seal Coat, aggregate No. 9 (washed), applied and compacted at 24 lbs per square yard	$ 32.00	$ 3,520.00	$ 26.00	$ 2,860.00	$ 25.00	$ 2,750.00
3	Spec.	1330	Gal	Fog Seal, SS-1H Dilute 50/50, Applied at 0.10-0.15 gal per square yard	$ 3.50	$ 4,655.00	$ 2.60	$ 3,458.00	$ 2.10	$ 2,793.00
4	614	1	L.S.	Maintaining Traffic	$ 400.00	$ 400.00	$ 500.00	$ 500.00	$ 500.00	$ 500.00
5	624	1	L.S.	Mobilization	$ 500.00	$ 500.00	$ 500.00	$ 500.00	$ 1,200.00	$ 1,200.00
6	103.05	1	L.S.	Contract Performance & Payment Bond	$ 312.50	$ 312.50	$ 300.00	$ 300.00	$ 200.00	$ 200.00
				Estimate Total		**$ 20,000.00**		**$ 18,655.00**		**$ 16,357.50**

(Richfield Township) Township Road 5 From State Route 281 to Township Road J
Length: 5290 Feet or 1 Mile(s)
Width: 18 Feet (Approx. 10660 S.Y. including radius and driveway work)
Type: Chip Seal, 1997 ODOT Spec 409 W/ Fog Seal

					Engineer's Estimate		Ward Construction Co.		Henry W. Bergman, Inc.	
Ref. #	Item	Quantity	Unit	Description	Unit Price	Total Price	Unit Price	Total Price	Unit Price	Total Price
1	409	4265	Gal	Seal coat, bituminous material (MWS 90) applied at 0.4 gallons per square yard	$ 2.50	$ 10,662.50	$ 2.60	$ 11,089.00	$ 2.10	$ 8,956.50
2	409	110	C.Y.	Seal Coat, aggregate No. 9 (washed), applied and compacted at 24 lbs per square yard	$ 32.00	$ 3,520.00	$ 26.00	$ 2,860.00	$ 25.00	$ 2,750.00
3	Spec.	1335	Gal	Fog Seal, SS-1H Dilute 50/50, Applied at 0.10-0.15 gal per square yard	$ 3.50	$ 4,672.50	$ 2.60	$ 3,471.00	$ 2.10	$ 2,803.50
4	614	1	L.S.	Maintaining Traffic	$ 400.00	$ 400.00	$ 500.00	$ 500.00	$ 500.00	$ 500.00
5	624	1	L.S.	Mobilization	$ 500.00	$ 500.00	$ 500.00	$ 500.00	$ 1,200.00	$ 1,200.00
6	103.05	1	L.S.	Contract Performance & Payment Bond	$ 245.00	$ 245.00	$ 300.00	$ 300.00	$ 200.00	$ 200.00
				Estimate Total		**$ 20,000.00**		**$ 18,720.00**		**$ 16,410.00**

(Richfield Township) Township Road J3 From County Road 6 to Township Road 5
Length: 5500 Feet or 1.04 Mile(s)
Width: 12 Feet (Approx. 7395 S.Y. including radius and driveway work)
Type: Chip Seal, 1997 ODOT Spec 409 W/ Fog Seal

					Engineer's Estimate		Ward Construction Co.		Henry W. Bergman, Inc.	
Ref. #	Item	Quantity	Unit	Description	Unit Price	Total Price	Unit Price	Total Price	Unit Price	Total Price
1	409	2960	Gal	Seal coat, bituminous material (MWS 90) applied at 0.4 gallons per square yard	$ 2.50	$ 7,400.00	$ 2.60	$ 7,696.00	$ 2.10	$ 6,216.00
2	409	75	C.Y.	Seal Coat, aggregate No. 9 (washed), applied and compacted at 24 lbs per square yard	$ 32.00	$ 2,400.00	$ 26.00	$ 1,950.00	$ 25.00	$ 1,875.00
3	Spec.	925	Gal	Fog Seal, SS-1H Dilute 50/50, Applied at 0.10-0.15 gal per square yard	$ 3.50	$ 3,237.50	$ 2.60	$ 2,405.00	$ 2.10	$ 1,942.50
4	614	1	L.S.	Maintaining Traffic	$ 400.00	$ 400.00	$ 500.00	$ 500.00	$ 500.00	$ 500.00
5	624	1	L.S.	Mobilization	$ 500.00	$ 500.00	$ 500.00	$ 500.00	$ 1,200.00	$ 1,200.00
6	103.05	1	L.S.	Contract Performance & Payment Bond	$ 262.50	$ 262.50	$ 300.00	$ 300.00	$ 200.00	$ 200.00
				Estimate Total		**$ 14,200.00**		**$ 13,351.00**		**$ 11,933.50**

Total Entire Bid	**$ 74,200.00**	**$ 69,446.00**	**$ 61,111.00**

Richfield Township awarded the project to Ward Construction Co.